

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan

(County)	Located In:	Corner Code #
	Lee Township	
1. Public Land Survey	T 1 N R 15 W	E-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

1994 DEC 16 AM 9:55
Register of Deeds Stamp & File Number
George J. Mitchell
REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

FILED

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, George J. Mitchell in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|-----|------------------------------|--------------------------------|
| E-1 | C. BRITAIN 1830 SET POSTAINS | RATEKIN WIT. CARD IRON |
| | PINE 30 S22W 11LKS | DOB POPLAR NE 43.7' GONE 94 |
| | BEECH 7 S72E 31 LKS | WILD CHERRY NW 34.8' GONE 94 |
| | T2N COR. WEST 126.40' | CLYDE COR. WEST 125.40 CK 1994 |
- RATEKIN 1978 LCRC FD PIPE G. BILOW 1993 FD 1-1/8" PIPE FROM LCRC
 NE COR HOUSE S20W 56.73' GONE 94 STOP SIGN N73W 69.4' CK 1994
 NW COR HOUSE S45W 65.97' GONE 94 DEADEND SIGN S83W 42.6' CK 1994
 10" TW OAK S75W 28.55 CK 1994 4" OAK S71W 30.87' CK 1994
 CLYDE CORNER WEST 125.41 CK 1994 PIPE IS ON SOUTH EDGE OF E-W ROAD

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- E-1 FOUND 1-1/8" PIPE FROM ABOVE WITNESSES AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 MEASURED 2610.77 FEET WEST TO D-1

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-29-94
 COUNTY REP. Handwritten Signature



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- E-1 SET 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.
- | | | |
|--|----------|---------|
| A.C. remon tag & nail in SW side of 8" Oak | AZ. 100° | 65.57' |
| A.C. remon tag & nail in SW side of 6" Oak | AZ. 155° | 70.69' |
| A.C. remon tag & nail in SE side of 12" Poplar | AZ. 235° | 81.53' |
| A.C. remon tag & nail in East side of 6" w. Cherry | AZ. 05° | 33.74' |
| Clyde Township Corner E-13 | AZ. 270° | 125.47' |
| Center of North-South asphalt road | AZ. 270° | 110.0' |

Signed by George J. Mitchell Date December 12, 1994
 Surveyor's Michigan License No. 19618

LIBREP 0005 PAGE 028