

**SURVEY  
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

.....ALLEGAN ..... Located in: LEE Township  
Corner Code #

1. Public Land Survey T..1..N R..15 W.....E-13.....  
T..... R..... SW COR, SEC 33

2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....

3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....

4. Lot No. ...., Recorded Plat .....

5. Private Claims.....

FILED

1/28/1999 2:44:39 PM

JOYCE A. MATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 006 PAGE 60

I, George J. Mitchell, in a filed survey on 10/26 thru 11/07/98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**A. Description of original monument and accessories and/or subsequent restoration:**

W. BROOKFIELD 1827 WEST ON SOUTH SIDE OF SECTION 33  
40.00 CHAINS SET POST 80.00 CHAINS PINE 24, CORNER TREE TO SEC 32 & 33

COUNTY SURVEYORS RECORDS 1966 IRON PIPE IN STAKE  
W. COR. HDW NE 58, HWY SIGN SOUTH 14.6', TREE WNW 72.65'  
TREE SW 24', VB COR. WEST 536.39', 2630.98 FEET TO S1/4 POST, SEC 32

G. MITCHELL P.S. 1984 FOUND IRON POWER POLE NE 67.2'  
15' COTTONWOOD SE 50.3' (STUMP REMAINS), 24' MAPLE SW 24.1'

G. MITCHELL P.S. 1994 FOUND 1" PIPE POWER POLE SW 39.65'  
30' MAPLE WSW 68.05', FACE/4" POPLAR 42.5' PK IN WEST SIGN POST SE 57.89'

G. MITCHELL P.S. 1998 FOUND 1" PIPE AND REMAINS OF WOOD STAKE  
MEASURED 2631.09 FEET TO S1/4 POST OF SEC 32., MEASURED 538.10 FEET TO VAN BUREN CORNER.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E-13) FOUND 1" PIPE AND REMAINS OF WOOD STAKE FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E-13) SOUTHWEST CORNER, SECTION 33, TOWN 1 NORTH, RANGE 15 WEST

REMOVED 1" PIPE AND SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. REMON TAG & NAIL IN SE. SIDE OF 30" MAPLE	AZ.	200°	25.20 FEET
A.C. REMON TAG & NAIL IN NW SIDE OF 24" MAPLE	AZ.	260°	138.80 FEET
A.C. REMON TAG & NAIL IN NE SIDE OF 30" MAPLE	AZ.	100	99.07 FEET
LEE TOWNSHIP SIGN POST	AZ.	010°	127.60 FEET

CORNER IS IN THE CENTER OF "T" INTERSECTION  
E-13 TO D-13 MEASURED 2631.09 FEET

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED NOV. 10, 1998  
COUNTY REP. [Signature]

Signed by George J. Mitchell  
Surveyor's Michigan License No. 19618

Date Nov. 11, 1998

