

SURVEY
REMONUMENTATION

APR 29 1999

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

.....ALLEGAN Township
Located in: Corner Code #

FILED

1/28/1999 2:44:39 PM

1. Public Land Survey T..1.N R..15 WF-13.....
T..... R..... S1/4 POST, SEC 33
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBER0006 PAGE 62

I, **George J. Mitchell**, in a filed survey on **10/26 thru 11/07/98** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	6	7	8	9	10	11	12	13	14	15	16	17
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

A. Description of original monument and accessories and/or subsequent restoration:

W. BROOKFIELD ¹⁸²⁷ ~~1827~~ WEST ON SOUTH SIDE OF SECTION 33 40.00 CHAINS SET POST
HEMLOCK 24 N36E 11 LKS HEMLOCK 20 N78W 26 LKS

COUNTY SURVEYORS RECORDS (NO DATE) STAKE & STONE
POWER POLE NNE 74.7' POWER POLE SE 81.5' GUY POLE NE 79.2'
STEEL FENCE POST NE 50' ST. SIGN SOUTH 14.2'

COUNTY SURVEYORS RECORDS (NO DATE) 1" AXLE SHAFT GUY POLE NW 55.2'
GUY POLE NE 63.5' GUY POLE NE 97.7' POWER POLE SE 81.65'

G. MITCHELL P.S. 1984, 1987, 1989, 1991 FD IRON P. POLE NE 74.82' G. POLE ENE 79.55' P. POLE SE 81.95'

G. MITCHELL P.S. 1994 FD 5/8" REBAR P. POLE SE 82.09' G. POLE ENE 79.54'
NAIL IN "WARNER CAMP" SIGN NW 81.06' T.C.B. NE 63.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13) FOUND 5/8" REBAR (8" LONG) OVER STONE & BROKEN BRICK FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13) SOUTH QUARTER POST OF SECTION 33, TOWN 1 NORTH, RANGE 15 WEST

REMOVED 5/8" REBAR AND STONE AND SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. REMON TAG & NAIL IN SO. LEG OF WARNER CAMP SIGN	AZ.	310°	80.95 FEET
A.C. REMON TAG & NAIL IN SOUTH SIDE OF GUY POST	AZ.	075°	79.75 FEET
A.C. REMON TAG & NAIL IN WEST LEG OF STREET SIGN	AZ	185	20.05 FEET
A.C. REMON TAG & NAIL IN NE SIDE OF POWER POLE	AZ	120°	82.10 FEET

CORNER IS IN THE CENTER OF "T" INTERSECTION

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED NOV. 10, 1998
COUNTY REP. [Signature]

Signed by George J. Mitchell
Surveyor's Michigan License No.19618.....

Date Nov. 11, 1998

