

**SURVEY  
REMONUMENTATION**

APR 29 1998

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

For corners in  
Allegan (County) Located In: Corner Code #

1. Public Land Survey T1N R15W G-1  
T R  
T R Lee Twp.  
T R

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

FILED  
1/28/1999 2:44:39 PM  
JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH  
Register of Deeds Stamp & File Number

LIDERO006 PAGE1,63

I, Donald R. Pitts, Jr., in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**  
1831 C. Britain 1969 County Surveyors Records  
Intersected town line 1.62 (106.92') E 1 1/2" Pipe  
of post 4" Pine SSE 23.6'  
Set post 20" Oak NNE 10.0'  
Pine 16 S 51 E 49' Centerline Road West 39.0'  
Aspen 4 S 77 W 29' 8" Oak E 49.7'  
10" Oak N 35.3'  
1969 County Surveyors Records Road Commission  
Found 1" pipe in centerline road P.K. in 14" Oak N 36.28'  
20" Oak NE 25.9' P.K. in 14" Oak NE 56.93'  
Power pole NE 62.0' P.K. in 12" Ash E 50.12'  
12" Twin Oak SE 32.3'  
9" Twin Oak W 53.4'  
24" Oak NW 52.7'

1991 George Mitchell  
Found iron  
24" Oak N 36.4'  
12" Pine S 10 E 23.8'  
Centerline road W 36.0'

1993 Gary Bilow - L.C.R.C. L4-P204  
Part "A": 1984 D. Bissell (P.S. 18655)  
Found 1 1/4" pipe  
S 64 W 61.43', 19" Oak  
N 35 E 10.70', 20" Oak  
N 83 E 49.96', 8" Oak  
S 15 E 23.62', 7" Pine  
CONTINUED ON REVERSE SIDE

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
Found 1/2" capped iron (DLB, P.S. 18655) 2.10 N of town line  
Center 22" Oak S 64 W 61.9' Nail and tag in 25" Oak N 35 E 10.70' Center 13" Oak N 83 E 49.7'  
Center 13" Pine S 15 E 24.0' SE Cor. Sec. 33, T2N, R15W, W 105.63' Centerline road W 39'  
P.K. in 14" Oak N 36.25' Center 14" Oak NE 56.9' Center 12" Ash E 49.7'  
17" Black Oak SW 73.23'

Pulled capped iron set Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520 on town line.

Approved by Allegan County Remonumentation Peer Group November 10, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner.

Traversed off road 2639' East and 2631' West

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED NOV. 10, 1998  
COUNTY REP. [Signature]

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520  
G-13, T2N, R15W, Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520  
West 105.63'  
Nail with Allegan County Remonumentation tag W side 12" Pine S 19 E 21.69'  
Nail with Allegan County Remonumentation tag SE side 24" Oak N 78 E 50.66'  
Nail with Allegan County Remonumentation tag SE side 18" Oak N 51 E 58.09'  
Nail with Allegan County Remonumentation tag S side 12" Oak N 30 E 12.28'



Signed by Donald R. Pitts, Jr. Date December 29, 1998  
Surveyor's Michigan License No. 23867

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY  
REMONUMENTATION

APP. 2 9 1933  
Continued from Sheet 1

SECTION

LIBERO 006 PAGE 64

A. Description of original monument and accessories and/or subsequent restoration:

Part "B": Found 1/2 capped iron all of Bissell's witnesses

Part "C": Found 1/2" capped iron  
S 64W 61.43', Nail and tag in 22" Oak  
N 35 E 10.70', Nail and tag in 25" Oak  
N 83 E 49.96', Nail and tag in 13" Oak  
S 15 E 23.62', Nail and tag in 13" Pine  
W 105.60', SE corner, Sec. 33, T2N, R15W

1993 Kirk L. Van Order  
Found capped iron D.L.B.  
26" Black Oak NE 10.67'  
12" Black Oak E 49.94'  
17" Black Oak SW 73.23'  
23" Black Oak WSW 61.42'

1994 Kirk L. Van Order  
Found capped iron D.L.B.  
Same witnesses as 1993