

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY Located in: LEE Township Corner Code #

- 1. Public Land Survey T.1 N.. R.15 W. G-8. WI/4 POST SEC. 22
2. Property Controlling S. T. R.
3. Miscellaneous S. T. R.
4. Lot No. Recorded Plat
5. Private Claims

REGISTER OF DEEDS ALLEGAN COUNTY

00 FEB - 1 AM 8:41

FILED

BOOK 001 PAGE 321

Register of Deeds Stamp & File Number

I, George J. Mitchell, in a field survey on October 5, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column G and row 8.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. C. BRITAIN D.S. 1831 - SET POST AT 40.00 CHAINS - PINE 30 S42W, 16 LKS & BEECH 12N45E, 20 LKS
2. OLD NOTES (NO DATE) IRON - OAK SE 29.5' & 2614' EAST TO CENTER
3. D. RATEKIN P.S. 1971 - L.C.R.C. L002, P028 - FOUND 1" IRON - STREET SIGN S45E 47.6' & T.C.B. S45W 47.1' NE COR. HOUSE S60W 91.2' & 16" TW. CHERRY N30E 73.4'
4. D. RATEKIN P.S. 1975 SAME AS L.C.R.C. ABOVE
5. J. DILLINGHAM P.S. 1980 FOUND 1" IRON - SAME WITNESSES AS ABOVE
6. G. MITCHELL P.S. 1986 FOUND 1" IRON - SAME WITNESSES AS ABOVE - MEASURED 2615.22' EAST TO CENTER
7. B. ANDRESS P.S. 1993 FOUND 1" IRON - 24" PINE N39E 115.21' & 34" PINE S22E 112.95' 20" TW. PINE S37W 55.59' & 27" PINE N45W 61.07' & MEAS 2615.05' EAST TO CENTER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON BAR FROM ITEMS 3, 6, AND 7 OF CORNER HISTORY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SET ALLEGAN COUNTY STANDARD 3/4" BY 24" IRON PIN WITH REMON CAP IN MON BOX

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON JUNE 8, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

WEST QUARTER POST OF SECTION 22, TOWN 1 NORTH, RANGE 15 WEST

- A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 24" PINE AZ. 039° 115.21 FEET
A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 20" TW PINE AZ. 215° 55.60 FEET
A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 27" PINE AZ. 325° 61.17 FEET
A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 30" PINE AZ. 080° 112.78 FEET
CENTER OF EAST-WEST ASPHALT ROAD NORTH 5'
CORNER LINES UP WITH CENTER OF ROAD TO NORTH

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED JUNE 8, 1999. COUNTY REP. [Signature]

Signed by George J. Mitchell Date 10/28/99

Surveyor's Michigan License No. 19618

