

**SURVEY
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
SECTION Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in <u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T1N R15W	H-1
	T R	
	T R	Lee Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

LIBERO 006 PAGE 66

I, Donald R. Pitts, Jr., in a field survey on October, 1 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Not set by Government 1991
George Mitchell
Found 5/8" iron
12" Oak SSE 18.30'
6" Oak E 18.00'
18" Pine NW 17.80'
Railroad tie fence post W 64.50'
1 1/2" pipe S 29.08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 5/8" iron and George Mitchell witnesses
East-West fence 7' South
Pulled 5/8" iron and set Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520.

Approved by the Allegan County Remonumentation Peer Group December 8, 1998. This position not established by original Government Surveyors. This monument is accepted as the best available evidence of the position of the corner.
Traversed off road 2605' East and 2639' West

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 8 1998
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520.
E-13, Town 2 North, Range 15 West, Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520
West 64.00'
Nail with Allegan County Remonumentation tag W side 8' Oak S 12 W 18.30'
Nail with Allegan County Remonumentation tag SW side 24" Pine N 37 W 17.78'
Nail with Allegan County Remonumentation tag NE side 12" Oak S 52 E 30.69'
Iron pipe S 01 E 29.08'



Signed by *Donald R. Pitts, Jr.* Date *December 29, 1998*
Surveyor's Michigan License No. 25867