

MAR 07 2000

GOVERNMENT CORNER HISTORY

SECTION

SOUTH QUARTER POST OF SECTION 10
TOWN 1 NORTH, RANGE 15 WEST

H-5

1. GLO NOTES
EAST ON RANDOM LINE BETWEEN SECT 10 & 15, SET TEMP POINT AT 40 CH. 79.72 CH TO EAST LINE OF SECT 20 LKS S. OF POST. WEST ON SECT LINE 39.86 CH. & SET POST.
18 W. OAK N55E 11 LKS
24 W. OAK S57W 29 LKS.
2. OLD NOTES MCDOUGHAL
STAKE & STONE
12" R. OAK NW 38.7'
14" B. CHERRY NE 43.7'
2625.7' EAST TO SE CORNER
3. D. RATEKIN P.S. (CARD)
IRON & STONE
S. GATE POST EAST 29.4'
18" CHERRY NNE 42.8'
SW COR COTTEGE NE 68.1'
POWER POLE NW 53.0'
22" OAK NW 38.8'
4. G. MITCHELL P.S. 1981
FD STONE & IRON
SAME WITNESSES AS ABOVE
5. R. MOORED P.S. 1989
1983
SURVEYS SHOW CORNER
NO WITNESSES
6. G. MITCHELL P.S. 1995
FD 1" IRON & STONE
POWER POLE SSW 103.79'
POWER POLE NNW 58.15'
18" OAK EAST 37.52'
CL ROAD WEST 9.0'
MEASURED 2632.72' NORTH TO CENTER
MEASURED 2625.04' EAST TO SE CORNER
7. G. MITCHELL P.S. 1999
JUNE 5, 199 - FD 1" IRON & STONE
MEASURED 2632.61' NORTH TO CENTER
MEASURED 2625.32' EAST TO SE CORNER
SET OFFSET STAKES AT 50 & 100 FEET TO THE SOUTHEAST
8. G. MITCHELL P.S. 1999
SEPTEMBER 30, 1999 - IRON & STONE REMOVED
DURING ROAD RECONSTRUCTION
RESET ALLEGAN CO. REMON FROM OFFSET STAKES SET JUNE 5, 1999

RECORDS / PAGE 33