

**SURVEY
REMONUMENTATION**

APR 29 1998

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

FILED

1/29/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 006 PAGE 68

For corners in <u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T1N R15W	I-1
	T R	
	T R	Lee Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Donald R. Pitts, Jr., in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1831 Calvin Britain
Intersected town line 94 lks (62.04) E of post - Set post
Maple 24 S 58 W 20
Birch 12 S 15 E 23

1988 R. J. Vugtveen - L.C.R.C., L4, P45
Found 1/2" pipe
Square spike in E side 4" Oak N 22 E 84.70'
Square spike in E side fence post S 48 W 33.33'
Center stop sign S 30 E 38.36'
Centerline 112th Avenue N 28.9'
Centerline 52nd Street E 3.4'

**APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY**

DATE APPROVED NOV. 10, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe
Square spike in E side 4" Oak N 22 E 84.45'
Square spike in E side fence post S 48 W 33.33'
Center stop sign S 30 E 38.36'
1/2" pipe with cap W 66.08'
Found railroad spike
1/2" pipe with cap W 68.72'

Pulled spike dug 3' to natural ground found nothing - replaced spike with 1/2" re-rod

Set Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520 on Town line 62.04' E of I-13, town 2 North, Range 15 West
Approved by the Allegan County Remonumentation Peer Group on NOVEMBER 10, 1998 and is accepted as a careful and faithful perpetuation of the position of the original corner.

Pulled 1/2" pipe L.C.R.C. Liber 4, Page 45 and 1/2" re-rod (railroad spike)

Traversed on road 5287' East

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520
I-13, Town 2 North, Range 15 West, Standard Allegan County Remonumentation 3/4"x36" iron with red cap #23520 West 62.04'
Top center telephone cable box S 32 W 41.53'
Nail with Allegan County Remonumentation tag E side 8" Oak N 29 E 73.98'
Nail with Allegan County Remonumentation tag W side 12" Ash S 15 E 87.76'



Signed by Donald R. Pitts, Jr.
Surveyor's Michigan License No. 25867

Date 29 December 1998