

RECORDED  
MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

ALLEGAN COUNTY..... Located in: ..LEE..... Township  
Corner Code #

- 1. Public Land Survey T.1 N.. R.15 W. ....I-6.....  
T..... R..... E1/4 POST SEC. 15
- 2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....
- 3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....
- 4. Lot No. ...., Recorded Plat .....
- 5. Private Claims.....

REGISTER OF DEEDS  
ALLEGAN COUNTY

00 FEB -1 11 8 42

FILED

RECORDED / FILED

Register of Deeds Stamp & File Number

I, .... **George J. Mitchell**....., in a filed survey on ...**October 5, 1999**.....  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner  
points mentioned in lines 1 and 2 above were in conformance with regulations and rules  
therefore as required in the current manual of survey instructions of the United States  
Department of the Interior, Bureau of Land Management or by decree of a Court of Law  
and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance  
with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law;  
established, re-established, monumented, re-monumented, recovered, found as expressed  
below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town & range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**I-6**

C. BRITAIN D.S. 1831 NORTH BETWEEN SECTIONS 14 & 15  
SET 1/4 POST AT 40 CHAINS  
10 PINEN62W 13 LKS  
8 PINE S36E 17 LKS

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 28, 1999  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND NO CORNER OR OCCUPATION. SET CORNER BY SINGLE PROPORTION BETWEEN NORTHEAST AND  
SOUTHEAST CORNERS OF THE SECTION. MEASURED 2636.98 FEET BOTH DIRECTIONS TO SECTION CORNERS.  
AND IS ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE POSITION OF THE ORIGINAL  
CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON DECEMBER 28, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

EAST QUARTER POST OF SECTION 15, TOWN 1 NORTH, RANGE 15 WEST  
ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP

A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 16" OAK	AZ.	150°	46.42 FEET
A.C. REMON TAG & NAIL IN WEST SIDE OF 16" OAK	AZ.	005°	43.70 FEET
A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 30" OAK	AZ.	045°	63.75 FEET
A.C. REMON TAG & NAIL IN NORTH SIDE OF 50" OAK STUMP	AZ.	270°	51.45 FEET
A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 16" OAK	AZ.	340°	56.04 FEET

CORNER IS LOCATED 8 FEET SOUTH AND 10 FEET WEST OF INTERSECTION OF OLD TRAILS

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED DEC. 28, 1999  
COUNTY REP. [Signature]

Signed by George J. Mitchell Date 12/30/99

Surveyor's Michigan License No. ....19618.....

