

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: ..LEE..... Township  
Corner Code #

1. Public Land Survey T.1 N. R.15 W. ....I-8.....  
T..... R..... E1/4 POST SEC. 22

2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....

3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....

4. Lot No. ...., Recorded Plat .....

5. Private Claims.....

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH.  
*George J. Mitchell*  
00 FEB -1 AM 8:42  
RECORDED  
FILED

Register of Deeds Stamp & File Number

I, .... **George J. Mitchell**....., in a field survey on ...**October 5, 1999**.....  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner  
points mentioned in lines 1 and 2 above were in conformance with regulations and rules  
therefore as required in the current manual of survey instructions of the United States  
Department of the Interior, Bureau of Land Management or by decree of a Court of Law  
and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance  
with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law,  
established, re-established, monumented, re-monumented, recovered, found as expressed  
below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-8

SEE SHEET 2 OF 2 FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" REBAR FROM ITEMS 4 AND 5 OF CORNER HISTORY, AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

SET ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON OCTOBER 12, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

EAST QUARTER POST OF SECTION 22, TOWN 1 NORTH, RANGE 15 WEST

A.C. REMON TAG & NAIL IN EAST SIDE OF 10" OAK	AZ.	005°	17.94 FEET
A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 16" OAK	AZ.	285°	25.04 FEET
A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 16" OAK	AZ.	110°	32.90 FEET
A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 12" OAK	AZ.	200°	40.43 FEET

CORNER IS LOCATED 5 FEET WEST OF OLD NORTH-SOUTH TRAIL  
I-8 TO I-9 MEASURED 2626.53 FEET  
I-8 TO H-8 MEASURED 2607.86 FEET

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED OCT. 12, 1999  
COUNTY REP. [Signature]

Signed by *George J. Mitchell* Date 10/28/99  
Surveyor's Michigan License No. ....19618.....



RF

MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY

EAST QUARTER POST OF SECTION 22  
TOWN 1 NORTH, RANGE 15 WEST

1 - 8

- 1. C. BRITAIN D.S. 1831 NORTH BETWEEN SECTIONS 22 & 23  
SET 1/4 SEC POST AT 40.00 CH.  
18 W OAK S81W 27 LKS  
24 PINE N77E 30 LKS
- 2. OLD NOTES NO DATE STAKE  
2615 WEST TO CENTER  
2630' SOUTH TO SE CORNER
- 3. D. RATEKIN P.S. 1981 PAPER LOCATION ESTABLISHED BY PROJECTING LINE  
NORTH FROM SE CORNER THROUGH E1/8 POST IN SE1/4,  
DOUBLING THE MEASURED DISTANCE OF 1313.37 FEET  
BETWEEN SE CORNER TO E1/8 POST.
- 4. G. MITCHELL P.S. 1987 SET 5/8" IRON AT ABOVE LOCATION  
8" OAK SW 12.75'  
8" OAK NORTH 17.95'  
6" CHERRY SSW 11.00'  
10" OAK SE 32.67'
- 5. R. VUGTEREEN P.S. 1998 FD 5/8" REBAR  
NO WITNESSES  
MEASURED 2626.20' SOUTH TO SE CORNER  
MEASURED 2607.33' WEST TO CENTER
- 6. G. MITCHELL P.S. 1999 FD 5/8" REBAR

000001 / 100319