

REMONUMENTATION

APR 25 1995

COMMISSION For corners in

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

ALLEGAN
(County)

Located In:

Corner Code #

1. Public Land Survey

T 1N R 15W

T-10 W 1/4 26
LEE TWP.

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1994 DEC 16 AM 9:55
 J. A. B. [Signature]
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

FILED

Register of Deeds Stamp & File Number

I, BASIL ADDRESS, in a field survey on 17 NOV, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	31	32	33	34	35	36	37	38	39	40	41	42
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- G.L.O. DON E. ALLEN, C.S.
 - 40.00 SET QR. SEC POST IRON
 - BEECH 15 N 69 W 30 FENCE POST NE 32.8'
 - HEMLOCK 14 S 56 E 24 ST. SIGN S 10.2'
 - W END DR. CULV SW 25'
 - OLD NOTES - COUNTY SURVEYOR
 - GUN BARREL
 - ELM 12 S 42
 - A.C.R.C. - 1930
 - STONE
 - 6" ELM S 50.3'
 - COR FENCE POST NE 38.9'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D. A. RATEKIN, C.S.
IRON
DIST E TO CENTER
2636.0'

FD. 1/2" IRON
DIST. E TO CENTER 2635.53'

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 7-12-94
COUNTY REP. [Signature]

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- REPLACED 1/2" IRON W/ STD. ALLEGAN CO. MON. (3/4" X 24" PIN & CAP)
 - SET 3/4" X 24" PINS & YELLOW REF. CAPS N 45 W 75.00' & 150.00'
 - E. EDGE STOP SIGN POST N 25 W 40.78'
 - W. EDGE W. LEG DIRECTION SIGN SOUTH 10.97'
 - 16d & REMON. TAG N SDE 12" POPLAR S 75 E 63.28'
 - C/L 103rd AVE. NORTH 6.0'



Signed by [Signature] Date 12 DEC 94
Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

REF: 0005 PAGE 029