

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: LEE..... Township
Corner Code #

1. Public Land Survey T.1 N., R.15 W.I-11.....
T..... R..... NW COR., SEC. 35
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

97 JAN 22 PM 1:24
 REGISTERED
 ALLEGAN COUNTY
 REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

I, DONALD R. PITTS, JR., in a filed survey on 10/15/95 & 12/03/96..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11

SEE SHEET 2 OF 2

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED 11-24-96
COUNTY REP. Rich J. Van Orden

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11

FOUND 1" IRON BAR FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 26, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11


SET ALLEGAN COUNTY STANDARD 3/4" BY 3/8" IRON PIN WITH REMON CAP.

A.C. REMON TAG & NAIL IN WEST SIDE OF 10" TWIN HICKORY	AZ.	350°	6.67 FEET
A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 12" TWIN HICKORY	AZ.	145°	32.73 FEET
A.C. REMON TAG & NAIL IN SOUTH SIDE OF 24" CHERRY	AZ.	085°	47.40 FEET
A.C. REMON TAG & NAIL IN NORTH SIDE OF 16" OAK	AZ.	260°	66.78 FEET
CENTER OF TWO TRACK DIRT ROAD	AZ.	180°	9.0 FEET
EAST END OF BRIDGE	AZ.	270°	80.2 FEET

Signed by Donald R. Pitts, Jr. Date 10 December 1996

Surveyor's Michigan License No. 25867

SHEET 1 OF 2



GOVERNMENT CORNER HISTORY
NORTHWEST CORNER OF SECTION 35
TOWN 1 NORTH, RANGE 15 WEST

I-11

BRITAIN D.S. 1831 NORTH BETWEEN SEC'S 34 & 35
40 CHAINS SET POST
76 CHAINS TO NORTH BANK OF STREAM
80 CHAINS TO RIVER AGAIN & SET CORNER POST
SYCAMORE 36 WEST 34 LKS
SYCAMORE 18 S43E 59 LKS

NOTE: FOUND IRON ON SOUTH BANK OF RIVER & RIVER CROSSES SECTION
LINE APPROX. 200 FEET SOUTH.

MITCHELL 1977 FD 1" IRON BAR
20" OAK SSE 46.46 FEET
E. END OF BRIDGE WEST 79.35 FEET
6" BASSWOOD WSW 39.95 FEET
IRON ON NORTH EDGE OF OLD ROAD
NOTES STATE THAT CORNER WAS FOUND FROM
INFORMATION FROM D.A. RATEKIN BUT NO
INFORMATION FOUND IN PACKET.

RECORDED & INDEXED

MITCHELL 1996 FD 1" IRON
24" OAK SSE 46.80 FEET
E. EDGE OF BRIDGE WEST 80.20 FEET
IRON ON NORTH EDGE OF OLD ROAD