

APR 07 1998 ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY Located in: ..LEE..... Township
Corner Code #

1. Public Land Survey T.1 N. R.15 W.I-12.....
T..... R..... W1/4 POST, SEC 35
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

98 JAN 21 PM 1:24
 REGISTER OF DEEDS
 ALLEGAN COUNTY MI

FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell, in a filed survey on 10/15/95 & 10/21/96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	0	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	18	20	21	22	23	24						
9												
10	30	28	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-12

H. BRITAIN - 1831
SET POST 40 CHAINS NORTH
B. ASH 15 N70E 20 LKS
HEMLOCK 9 S39W 9 LKS

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 3-11-97
COUNTY REP. K.V.O.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12

FOUND NO EVIDENCE OF ANY CORNER. SET CORNER AT MIDPOINT ON LINE BETWEEN NORTHWEST AND SOUTHWEST CORNERS OF THE SECTION AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

NOTE: AFTER THE CORNER WAS SET, FENCE WAS FOUND IN TREES TO THE EAST AND WEST AND TO THE NORTH.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON MARCH 11, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12

SET ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP.

A.C. REMON TAG & NAIL IN WEST SIDE OF 18" ASH WITH EMBEDDED FENCE	AZ.	270°	22.85 FEET
A.C. REMON TAG & NAIL IN EAST SIDE OF 24" ASH WITH EMBEDDED FENCE	AZ.	00°	60.75 FEET
A.C. REMON TAG & NAIL IN SOUTH SIDE OF 10" HICKORY	AZ.	265°	9.10 FEET
A.C. REMON TAG & NAIL IN NORTH SIDE OF 20" MAPLE & EMBEDDED FENCE	AZ.	90°	46.67 FEET

Signed by George J. Mitchell Date March 12, 1997

Surveyor's Michigan License No.19618.....