

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: LEE Township
Corner Code #

1. Public Land Survey T.1 N. R.15 W.1-13.....
T..... R..... SW COR., SEC. 35
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

97 JUN 22 11 1:24
REGISTER OF DEEDS
ALLEGAN COUNTY
MICHIGAN
FILED

Register of Deeds Stamp & File Number

I, DONALD R. PITTS, JR., in a filed survey on 10/15/95 & 12/03/96..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13

SEE SHEET 2 OF 2

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-26-96
COUNTY REP. Neil E. Van Orden

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13

FOUND 3/4" REBAR FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 26, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13


SET ALLEGAN COUNTY STANDARD 3/4" BY 3/8" IRON PIN WITH REMON CAP.

A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 24" TW. OAK	AZ.	330°	61.35 FEET
A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 14" POPLAR	AZ.	140°	55.55 FEET
A.C. REMON TAG & NAIL IN NORTH SIDE OF 12" POPLAR	AZ.	192°	33.56 FEET
A.C. REMON TAG & NAIL IN EAST SIDE OF 10" MAPLE CLUMP (6 TREES)	AZ.	020°	36.60 FEET

Signed by Donald R. Pitts, Jr. Date 10 DECEMBER 1996

Surveyor's Michigan License No. 25867

SHEET 1 OF 2



GOVERNMENT CORNER HISTORY
SOUTHWEST CORNER OF SECTION 35
TOWN 1 NORTH, RANGE 15 WEST

I-13

BRITAIN D.S. 1831	WEST ON SOUTH SIDE OF SECTION 35 40.00 CHAINS SET POST 80.00 CHAINS SET POST FOR SEC'S 34 & 35
MITCHELL 1976	SET 5/8" IRON 742 FEET WEST OF N1/8 POST, NW1/4, SECTION 3, T1S, R15W AS PER D.A. RATEKIN 28" OAK CLUSTER NNW 18.58 FEET 8" POPLAR SW 18.56 FEET 2" IRON ENE 20.18 FEET IRON WAS SET BY EXTENDING LINE FROM S1/4 POST THRU 1/8 POST IN SEC 3 COLUMBIA TWP.
MITCHELL 7/28/77	L.C.R.C LIBER 3, PAGE 181 SAME WITNESSES AS ABOVE
MITCHELL 1986	FD 5/8" IRON 6" MAPLE CLUSTER N10E 36.0 FEET 18" TWIN OAK N40W 60.4 FEET 10" POPLAR S45E 55.4 FEET
MITCHELL 1996	FD 5/8" IRON 24" TW. OAK N30W 61.35 FEET 10" MAPLE CLUSTER N15E 36.60' 14" POPLAR S50E 55.55 FEET IRON FD ON OCCUPATION TO NORTH