

**SURVEY
REMONUMENTATION**

APR 29 1999

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Allegan
(County)

Located In: _____ Corner Code # _____

1. Public Land Survey T1N__ R15W__ J-1
T__ R__
T__ R__ Lee Twp.
T__ R__

2. Property Controlling S__ T__ R__
in Section S__ T__ R__
3. Miscellaneous S__ T__ R__
Property in Sec. S__ T__ R__

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
Register of Deeds Stamp & File Number

LIBERO 006 PAGE 69

I, Donald R. Pitts, Jr., in a field survey on October 1, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Not set by Government

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" iron with witness nails 6.46' S of Town line and 1.29' E of being equidistant I-1, T1N, R15W and K-1, T1N, R15W

Set Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520 on town line.

Equidistant From I-1, Town 1 North, Range 15 West and K-1, Town 1 North, Range 15 West.

Approved by the Allegan County Remonumentation Peer Group ^{November 10} ~~December 8~~, 1998. This position not established by original Government Surveyors. This monument is accepted as the best available evidence of the position of the corner.

Pulled found 1/2" iron.

Traversed on road 2626' East and 2626' West.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED Nov. 10, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520.
- J-13, Town 2 North, Range 15 West Standard Allegan County Remonumentation 3/4"x24" iron with red cap #23520 West 44.14'
- Nail with Allegan County Remonumentation tag NW side 12" Twin Oak N 05 W 59.52'
- Nail with Allegan County Remonumentation tag W side 10" Maple S 15 W 37.65'
- Nail with Allegan County Remonumentation tag NW side 6" Pine N 64 W 74.05'



Signed by [Signature]
Surveyor's Michigan License No. 25867

Date December 29, 1998