

SURVEY & REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
ALLEGAN
(County)

	Located in:	Corner Code #
1. Public Land Survey	T-1N R-15W	J-9 N 1/4 26
	T R	LEE TWP.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1994 DEC 16 AM 9:55
 Roger A. Lettice
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN

FILED

Register of Deeds Stamp & File Number

I, BASIL ADDRESS, in a field survey on 18 NOV, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | | |
|------------------------------------|---------------------------|--------------------------|
| G.L.O. | DON E. ALLEN, C.S. | GEORGE J. MITCHELL, P.S. |
| WEST CORRECT B/WN SECTIONS 23 & 26 | 1" IRON | L.C.R.C. L-3, P-184 |
| 39.98 SET QR. SEC POST | 26" MAPLE SW 34.3' | 1" IRON |
| PEPPERAGE 24 N 87 E 10 | 21" MAPLE SE 41.0' | 26" MAPLE SW 34.3' |
| HENLOCK 6 S 67 W 16 | 23" W. CHERRY NNE 57.1' | 21" MAPLE SE 41.0' |
| OLD NOTES - COUNTY SURVEYOR | DONALD A. RATEKIN, C.S. | 23" CHERRY NNE 57.1' |
| STAKE | IRON | 12" MAPLE NNE 28.1 |
| DIST. S TO CENTER 2637.5' | DIST. S TO CENTER 2638.8' | 30" MAPLE SE 41.55' |
| | | 36" MAPLE SW 36.0' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1" IRON
 CHECKS W/ MITCHELL'S WITNESSES
 DIST. S TO CENTER 2640.13'
 1/2" IRON W/ CAP (#19618) SOUTH 33.00'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 7-12-94
 COUNTY REP. Basil J. Address, Jr.

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" IRON W/ STD. ALLEGAN CO. MON. (3/4" X 24" PIN & CAP)

16d & REMON TAG SW SDE 16" W. CHERRY S 50 E 59.83'
 16d & REMON TAG SE SDE 18" MAPLE N 30 E 93.62'
 16d & REMON TAG NW SDE 3" BEECH N 50 E 62.24'
 FD SPK NW SDE 42" MAPLE S 50 W 35.88'
 FD SPK SW SDE 32" MAPLE S 60 E 41.43'
 1/2" IRON W/ CAP (#19618) SOUTH 33.00'
 IN C/L 104th AVE



Signed by Basil J. Address, Jr.
 Surveyor's Michigan License No. 30075

Date 12 DEC 94

LIBR 0005 PAGE 030