

# SURVEY & REMONUMENTATION

APR 25 1995

## ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**  
ALLEGAN  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>15W</u>	<u>K-10 E1/4 26</u> <u>LEE TWP.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 1994 DEC 16 AM 9:55  
 FILED

Register of Deeds Stamp & File Number

I, BASIL ADDRESS, in a field survey on 17 NOV, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	15	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.  
NORTH BTWN SECTIONS 25 & 26  
40.00 QR. SEC POST IN LAKE

OLD NOTES CONT.  
SHOW ANGLE N TO W 89DEG-34'  
DIST. N TO NE COR 2638.8'  
DIST W TO CENTER 2636'

OLD NOTES - COUNTY SURVEYOR  
SHOW STONE W/"X" ON E & W 1/4  
LINE AT WEST SIDE OF LAKE  
SHOWS E & W 1/4 LINE DIVIDED INTO  
4 EQUAL SEGMENTS (1318.7')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1" IRON OVER STONE W/"X" ON E & W 1/4 LINE WEST OF K-10

WEST TO CENTER: S 90DEG-00'-00" W 2190.18'  
CONT. WEST TO W 1/4 COR N 89DEG-56'-20" W 2635.53'

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 7-12-94  
COUNTY REP. [Signature]

ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" IRON & STONE W/ STD. ALLEGAN CO. REF. MON. (3/4" X 24" PIN & YELLOW CAP)

- 16d & REMON TAG SW SDE 12" OAK N 65 W 90.85'
- 16d & REMON TAG NW SDE 26" OAK S 65 W 91.87'
- 16d & REMON TAG NW SDE 24" OAK S 55 W 56.05'
- 16d & REMON TAG W SDE 30" SYCAMORE S 15 E 140.09'
- 16d & REMON TAG S SDE TWIN MAPLE (8"-32") S 70 E 56.95'
- C/L 50th ST. WEST 4.0'



Signed by [Signature]  
Surveyor's Michigan License No. 30075

Date 12 DEC 94

REFR 0005 PAGE 031