

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: ...LEE..... Township  
Corner Code #

1. Public Land Survey T.1 N. R.15 W. ....K-11.....  
T..... R..... NE COR., SEC. 35
2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....
4. Lot No. .... Recorded Plat .....
5. Private Claims.....

97 JAN 22 PM 1:24  
 FILED  
 ALLEGAN COUNTY  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, ...DONALD R. PITTS, JR....., in a filed survey on ...10/15/95 & 12/03/96..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				7	7					
3												
4	7	8				10	11			13		
5												
6	18	17			18	15			14		13	
7												
8	19	20			21	22	23		24			
9												
10	30	29			28	27	26		25			
11												
12	31	32			33	34			35		36	
13												

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11

SEE SHEET 2 OF 2

**APPROVED REMONUMENTATION CORNER**  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 11-26-96  
 COUNTY REP. Donald R. Pitts, Jr.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11

FOUND 1" PIPE OVER 3/4" REBAR FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 26, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11


SET ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP.

A.C. REMON TAG & NAIL IN NORTH SIDE OF 40" OAK	AZ.	270°	15.46 FEET
A.C. REMON TAG & NAIL IN WESTERLY SIDE OF 36" OAK	AZ.	345°	76.45 FEET
A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF TELEPHONE POLE	AZ.	135°	53.85 FEET
A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 14" RED PINE	AZ.	040°	56.08 FEET
CENTER OF NORTH-SOUTH ROAD	AZ.	090°	2.5 FEET

Signed by Donald R. Pitts, Jr. Date 10 December 1996

Surveyor's Michigan License No. 25867

SHEET 1 OF 2



GOVERNMENT CORNER HISTORY  
NORTHEAST CORNER OF SECTION 35  
TOWN 1 NORTH, RANGE 15 WEST

K-11

L. LYON D.S. 1831      NORTH BETWEEN SECS 35 & 36  
40 CHAINS SET POST  
60.00 CHAINS SET POST FOR SEC'S 25, 26, 35 & 36  
BEECH      CORNER TREE

RATEKIN OLD NOTES      ST. SIGN      WNW 11.4      GONE 1996  
30" OAK      WEST 14.9      CK 1996  
TEL POLE      SE 45.2      GONE 1996  
8" ELM      NE 57.2      GONE 1996

RATEKIN      1972      L.C.R.C. LIBER 2, PAGE 88  
1" BOLT  
32" OAK      S80W 14.9'      CK 1996  
CL T.C.B.      S45E 53.2'      CK 1996  
CL T.C.B.      N45E 54.8      CK 1996'  
ST. SIGN      N80W 11.4'      GONE  
7" CHERRY      S60W 18.8'      GONE

RATEKIN      1979      FD IRON  
ST. SIGN      WNW 11.4      GONE 1996  
30" OAK      WEST 14.9      CK 1996  
CL T.C.B.      N45E 54.8      CK 1996  
CL T.C.B.      S45E 53.2      CK 1996

MITCHELL 1996      FD 1" PIPE OVER 3/4" REBAR  
1" PIPE WAS CAPPED BY RAY MOORED  
ABOVE WITNESSES CHECK AND DISTANCE SOUTH TO  
1/8 POST AND E1/4 POST CHECK RATEKIN CARD FILE.