

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS
ALLEGAN COUNTY MICH.
James A. ...

00 FEB - 1 AM 8:42

LIBER0007 PAGE 354
FILED

SECTION

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN: LEE TOWNSHIP	CORNER CODE #
1. Public Land Survey	T...1:N. R.15:W	...M:11....
SOUTHEAST CORNER OF SECTION 25, T.1N, R.15W.	T..... R.....
NORTHEAST CORNER OF SECTION 36, T.1N, R.15W.	T..... R.....
	T..... R.....
2. Property Controlling in section	S..... T..... R.....
	S..... T..... R.....
3. Miscellaneous Property in Sec.	S..... T..... R.....
4. Lot No..... Recorded Plat.....		
5. Private Claims.....		

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Raymond Moored in a field survey on Aug. 5, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR GOVERNMENT CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED OCT. 12, 1999
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE PER. NUMBER 3 AND 4 ON BACK OF THIS FORM.
REMOVED AND SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.
APPROVED BY THE ALLEGAN COUNTY REMON PEER GROUP ON OCT. 12, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP		
-FOUND NAIL IN POWER POLE	NORTH	31.0'
-SW CORNER GARAGE	N25E	64.60'
-C/L EAST-WEST ROAD	SOUTH	64.5'
-W. END 12" CMP DRIVE CULVERT	S25E	51.40'
-A-11, T.1N., R.14W.	SOUTH	107.58'

Raymond Moored
Date 12/15/99

Surveyors License No. 26463



RE...

MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY
M-11
NORTHEAST CORNER OF SECTION 36
TOWN 1 NORTH, RANGE 15 WEST,

LIBER 007 PAGE 355

- 3. ~~2~~ COUNTY SURVEYOR NOTES: 3/4 PIPE
 - STOP SIGN S. SE 41.6
 - POWER POLE N 31.0
 - SW CORNER GARAGE NE 64.6

- 1. ~~2~~ Wm BROOKFIELD, DEPUTY SURVEYOR, 1837: SET POST

- 2. ~~3~~ HUGH Mac DOUGAL, COUNTY SURVEYOR CIRCA 1900'S
LEGAL DESCRIPTION OF BRUSH CREEK DRAIN NOTING TOWNLINE AND SECTION
CORNER.

- 4. D.A. RATEKIN, COUNTY SURVEYOR: SECTION CARD
3/4 INCH IRON RESET WITH 1 INCH IRON IN 1971
SAME WITNESSES AS NO. 1

- 5. D.A. RATEKIN, COUNTY SURVEYOR; L.C.R.C. LIBER 1 PAGE 128
WITNESSES AND CORNER SAME AS NO.1 & NO.4

- 6. D.A. RATEKIN, COUNTY SURVEYOR: SURVEY 3-11-71 NO WITNESSES

- 7. D.A. RATEKIN, COUNTY SURVEYOR: SURVEY 8-26-71
WITNESSES SAME AS NO. 1 & NO. 4

- 8. WIGHTMAN-MOORED, INC.: SURVEY 12-21-90 NOTES CORNER
NO WITNESSES

- 9. WIGHTMAN-MOORED, INC.: SURVEY 1-27-92 NOTES CORNER
NO WITNESSES

- 10. HOLLAND ENGINEERING, SECTION CARD NOTES CORNER
SAME WITNESSES AS NO. 1 & NO.4