

RE...

MAR 6 7 2000

SECTION

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

REGISTER OF DEEDS ALLEGAN COUNTY MI 49700
Spencer A. ...

00 FEB - 1 AM 8:42

FILED LINGR0007 PAGE 356

FOR CORNERS IN: ALLEGAN COUNTY

1. Public Land Survey

LOCATED IN: T...1N... R15W... M:12.....

EAST 1/4 POST of SECTION 36, T1N, R15W. LEE TWP.

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No....., Recorded Plat.....

5. Private Claims.....

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Raymond Moored in a field survey on AUG. 5, 1999 do hereby state that under equipments of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED OCT. 12, 1999 COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON WITH CAP PER ITEMS NUMBER 2 & 3 LISTED ON BACK OF SHEET.

SET 3/4" X 24" ALLEGAN COUNTY REMON IRON WITH CAP IN PLACE OF FOUND CORNER. ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMONUMENTATION PEER GROUP ON OCT. 12, 1999.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 24" ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.

CORNER of ELECTRIC BOX S 30 W 50.75' C/L ROAD TO WEST SOUTH 10.5' NAIL & TAG IN E. SIDE 18" SYCAMORE N 80 W 63.80' C/L END of 60' CMP N 30 W 56.80' C/L END of 60' CMP N 20 E 31.80' SOUTH 53.70' A-12, T1N, R14W,

[Signature] Date 12/15/99

Surveyors License No. 26463



MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY
M-12
TOWN 1 NORTH, RANGE 15 WEST,
LEE TOWNSHIP, ALLEGAN COUNTY, MICHIGAN

1. Wm. BROOKFIELD, DEPUTY SURVEYOR; MAY 12, 1837
 NOTES: 2.00 STREAM 40 LINKS WIDE @ S.W.
 23.17 BEECH 12.
 40.00 SET SECTION POST
 ALDER 4S48W39
 ALDER 4S39W20

2. D.A. RATEKIN COUNTY SURVEYOR; CIRCA 1970'S
 SECTION CARD NOTES EAST ¼ POST WITNESSES AS;
 24" SYCAMORE S 40°E 98.6'
 ST. SIGN S 35°E 25.90'
 NAIL IN 18" WALNUT N 80°W 54.85'
 NAIL IN 18" WALNUT S 30°W 25.35'

3. D.A. RATKIN, COUNTY SURVEYOR; CIRCA 1970'S
 L.C.R.C. LIBER 1, PAGE 129, NOTES WITNESSES AS:
 SAME AS ITEM # 2

4. D.A. RATEKIN, COUNTY SURVEYOR; CIRCA 1970'S
 SURVEY FOR J. STROTH NOTES WITNESSES AS:
 SAME AS ITEM #2

5. HOLLAND ENGINEERING,
 SECTION CARD NOTES WITNESSES AS:
 SAME AS ITEM #2

LIBER 007 PAGE 57

