

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>1</u> N. <u>X</u> R. <u>15</u> IX W.	K-5, I-5, J-5, J-4-
2. PROPERTY CONTROLL- ING IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**RECORDED**

**Dec 26 10 57 AM 1972**

**REGISTER OF DEEDS**  
ALLEGAN COUNTY, MICH.

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Douglas W. Bonnema do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on November 6, 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

K-5 Found 3/4" iron. Checks with previous witnesses.	I-5 Found 1/2" solid iron. Checks with previous witnesses.	J-5 Set 3/4" iron on straight line between SE & SW Sec. Corners and at midpoint. Checks with previous witnesses.	J-4 Found 1 1/4" iron in monument box. Checks with previous witnesses.
--	--	--	--

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-5 3/4" iron. Nail in side P. Pole SE 39.98 Nail in side 12" Poplar NW 55.51 ¢ Independent junction box WNW 31.87 ¢ gravel road E 8	I-5 1/2" iron. Nail in side 20" Oak SW 54.24 Nail in side 10" Oak NW 31.49 Nail in side T. Pole E 27.71	J-5 3/4" iron. Nail in side 16" Oak SW 20.41 Nail in side 12" Oak SE 28.14 Nail in side 10" Oak NE 24.71 Nail in side 14" Oak NNW 55.72	J-4 1 1/4" iron. Nail in side 18" W. Cherry NNW 43.95 Nail in side 10" Oak NE 53.03 SW corner block pillar SE 65.34
---	---	--	---


SIGNED BY Douglas W. Bonnema DATE November 24, 1972  
EXCEL ENGINEERING, P.C.

SURVEYOR'S MICHIGAN REGISTRATION NO. 12579

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



PAGE 120

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_