

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN

(County)	Located In:	Corner Code #/
1. Public Land Survey	T 1N R 15W	M1
	T 1N R 15W	M2
	T 1N R 15W	M3
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, GARY C. BILOW, in a field survey on April 10, 1991, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- (M1) CORNER POST ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR LUCIUS LYON, 1831. ACCESSORIES: W. OAK 12 N30W 39, PINE 8 S18W 13. 1897 PERSONAL RECORD OF FORMER COUNTY SURVEYOR HUGH MacDOUGALL SHOW "STAKE AND BRICK, OAK 10" NW 35.2". WITNESSES FROM ALLEGAN CO. RD. COMMISSION INCLUDE: 25" OAK WNW 35.0', 5" TWN OAK SW 42.0', PP NW 58.7'.
- (M2) CORNER POST ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR LUCIUS LYON, 1831. ACCESSORIES: PINE 8" S12W 14, PINE 18" N19 1/2W 37. PERSONAL RECORD OF FORMER ALLEGAN COUNTY SURVEYOR HUGH MacDOUGALL (ca. 1897) SHOWS "STAKE". NO ACCESSORIES NOTED. FOUND NO OTHER RECORD OF PERPETUATION.
- (M3) CORNER POST ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR LUCIUS LYON, 1831. ACCESSORIES: BOXWOOD 8 S19W 15, THORN 4 N24W 30. PERSONAL RECORD OF FORMER ALLEGAN COUNTY SURVEYOR HUGH MacDOUGALL (ca. 1897) SHOWS OAK STAKE SET FROM SW CORNER SECTION 6, T1N-R14W. ACCESSORIES NOTED ARE ILLEGIBLE. FOUND NO OTHER RECORD OF PERPETUATION.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (M1) FOUND AND ACCEPTED 1" IRON BAR 10" BELOW GRAVEL SURFACE. FROM THIS BAR, MacDOUGALL AND ACRC TIE TO OAK NW FITS THE STUMP HOLE OF A LARGE OAK STUMP REMOVED BY OTHERS BETWEEN MARCH 1, AND MARCH 12, 1991. OTHER ROAD COMMISSION TIES NOTED ABOVE CHECK.
- (M2) ORIGINAL POST AND ACCESSORIES NOT RECOVERED. FOUND NO MONUMENTATION AT THIS LOCATION. RECOVERED ANCIENT BARBED WIRE FENCE INTERSECTION BENEATH LEAF DUFF. DID NOT FIND REMAINS OF CORNER FENCE POST. OLD WIRE RUNS SOUTH AND WEST, COMPLETELY COVERED BY FOREST DEBRIS. I NOTE THAT THE FENCE INTERSECTION IS 7.3' SOUTH AND 9.6' EAST OF THE PROPORTIONATE POSITION AND ACCEPT THE INTERSECTION AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER LOCATION. AT THE POSITION FOR THE CORNER I PLACED A 1/2"x36" REBAR ENCASED IN A 4" DIAMETER CONCRETE CYLINDER CAPPED WITH A CAST ALUMINUM MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET.
- (M3) ORIGINAL POST AND ACCESSORIES NOT RECOVERED. FOUND AND ACCEPTED A 3/4" IRON BAR, 155.79' NORTH OF MONUMENTED SW CORNER OF SECTION 6, T1N-R14W (GLO RECORD 2.42 CH.). BAR CHECKS WITH U.S. GOVERNMENT MEASURE NORTH TO M2 (-7.5') AND SOUTH TO M4 (+1.0'). PLACED A 1"x48" IRON PIPE WITH CAST ALUMINUM MDNR TABLET OVER BAR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|--|--|
| (M1) FOUND 1" IRON BAR
S41E 39.90' SET NAIL AND MDNR TAG IN EAST FACE 10" OAK; S02W 32.99' RAILROAD SPIKE IN 16" W. OAK; S52W 42.03' SET NAIL AND MDNR TAG IN NORTH FACE 11" TWIN OAK; N54W 59.11' SET NAIL AND MDNR TAG IN EAST FACE POWER POLE; CORNER IS AT CENTERLINE INTERSECTION OF ROADS NORTH, WEST, AND EAST. | (M2) SET CONCRETE MONUMENT WITH MDNR CAP N10W 29.35' SET NAIL AND MDNR TAG IN WEST FACE 9" RED OAK; N32E 29.76' SET NAIL AND MDNR TAG IN NW FACE TWIN 8" CHERRY; S69E 18.34' SET NAIL AND MDNR TAG IN NORTH FACE 9" WHITE OAK; S61W 16.60' SET NAIL AND MDNR TAG IN SOUTH FACE 8" WHITE OAK. | (M3) SET 1"x48" CAPPED IRON PIPE OVER 3/4" BAR: S35W 10.87' SET NAIL AND MDNR TAG IN EAST FACE 6" ASH; N65W 4.15' SET NAIL AND MDNR TAG IN SOUTH FACE TWIN ASH; N25E 6.29' SET NAIL AND MDNR TAG IN EAST FACE TWIN MAPLE; S03E 155.79' 1 1/4" PIPE AT SW CORNER SECTION 6, T1N-R14W; SOUTH 46' CENTERLINE OF GRAVEL ROAD |
|---|--|--|

Signed by Gary C. Bilow Date 8/1/91
 Surveyor's Michigan License No. 26453

