

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
**ALLEGAN**

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>1N</u> R <u>15W</u>	<u>F4</u>
	T <u>1N</u> R <u>15W</u>	<u>K4</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, GARY C. BILOW, in a field survey on April 10 (K4), May 3 (F4), 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9	10			11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(F-4) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. CORNER RECORDED UNDER ACT 74, P.A. 1970 BY DAVID PEABODY, RLS #25866 IN 1979 AS "MON BOX". PEABODY'S ACCESSORIES ARE AS FOLLOWS: CONC. BLOCK PILLAR S35E 38.6', P. POLE S45W 53.3', 32" OAK N20W 54.0' (RECORDED IN LIBER 3, PAGE 261 OF LAND CORNER CERTIFICATES).

(K-4) ORIGINAL CORNER POST ESTABLISHED BY U.S. GOVERNMENT DEPUTY SURVEYOR C. BRITAIN, 1831. ACCESSORIES: PINE 18 S31E 13, DO 9 N31W 12. NOTES OF RAY MOORED R.L.S. #26463 SHOW "PLOW POINT, TP SE 63.7', PP NW 52.2', ST. SIGN SW 36.7', PP SW 51.2', TP NE 53.9'".

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(F-4) FOUND 1 1/4" IRON BAR IN MONUMENT BOX IN ACCORD WITH RECORD ACCESSORIES AS FOLLOWS: NE FACE OF POWER POLE S51W 53.3', 32" OAK N19W 54.0'.

(K-4) FOUND 1" IRON BAR IN MONUMENT BOX WITH MOORED'S TIES TO POWER POLES NW AND SW AGREEING. ACCEPTED SAME AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER LOCATION. I USED THIS CORNER TO REESTABLISH K-3, AS NOTED IN THE LAND CORNER RECORD THIS DATE.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(F-4) FOUND 1 1/4" IRON BAR IN MONUMENT BOX: N40E 39.10' SET NAIL AND MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN EAST FACE GUY POLE; S22E 42.4' STOP SIGN POST; S51W 53.87' NAIL IN SE FACE POWER POLE; N19W 55.45' SET NAIL AND MDNR TAG IN EAST FACE 32" OAK

(K-4) FOUND 1" IRON BAR IN MONUMENT BOX N40W 52.54' PK WITH TAG IN EAST FACE GUY POLE; N45E 79.48' PK WITH TAG IN WEST FACE POWER POLE; S45W 51.62' PK WITH TAG IN EAST FACE TRANSFORMER POLE; NORTH 2' CENTERLINE OF BITUMINOUS SURFACE OF 109th AVENUE.



Signed by Gary C. Bielow  
 Surveyor's Michigan License No. 26453

Date 8/1/91

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983