

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY Sec. 2 T. 1 N. R. 15 E.		K-1
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER
 REGISTERED DEEDS
 REGISTERED
 1988 NOV -3 AM 8 44
 FILED

I, Randal J. Vugteveen, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 19, 19 88 established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-1: 1906 notes from Allegan County Surveyors Office calls for stone 28.38 feet East of SE corner Section 35, T2N, R15W and 3008 feet (Gov't = 3005.64) from the E 1/4 corner Section 2, T1N, R15W

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-1: Found pointed stone with pieces of iron, 26.35 feet East of SE corner Section 35, T2N, R15W, (2" X 6" iron) and 3006.14 feet North of E 1/4 corner Section 1, T1N, R15W. Set capped iron above. This is 4.5 feet South and 16 feet East of capped iron previously recorded as NE corner Section 2, T1N, R15W in Liber 003, Page 364.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1: Capped iron
 SE corner Section 35, T2N, R15W, (2" X 6" iron) N90°W 26.35'
 sq. spike in NW side 40" red oak S50°W 37.35'
 sq. spike in NE side 14" red pine N52°W 72.72'
 sq. spike in SE side 10" white oak N42°E 54.77'
 sq. spike in SW side 20" twin oak S54°E 55.49'
 centerline 112th Avenue North 7'
 centerline 60th Street East 5'



SIGNED BY Randal J. Vugteveen DATE 10-31-88
 Randal J. Vugteveen, Nederveld Associates Surveying, Inc.
 SURVEYOR'S MICHIGAN REGISTRATION NO. 28429

FOR STATE AND UNITED STATES AGENCIES:
 SIGNED BY _____ DATE _____
 CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
 MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____
 THIS CERTIFICATE IS VALID ONLY WHEN ATTACHED TO THE ORIGINAL SURVEY MAP OR PLAT.
 APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 26, 1971
 REVISED MAY 12, 1978