

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970<sup>21</sup>

3.00 FE

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>1</u> T. <u>1</u> N. R. <u>15</u> W.		L-1 K-1 K-2
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ S. R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS  
ALLEGAN COUNTY MICH.

*John H. Dillingham*

Oct 24 4 22 PM '83

FILED

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John H. Dillingham do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 18, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

L-1 No record of corner                      K-1 Stake                      K-2 Stone

ALL VOID

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L-1 Found 8 1/4" Post and center of Sec. Ran straight line over two corners and set N 1/4" Post on proportional measurer to distances on record in Allegan County Records. Set 1/2" iron rod and Cap.	K-1 Reset corner on straight line and double distance from the NE Cor. to the N 1/4" Post as shown on record in Allegan County. Set 1/2" Iron Rod & Cap	K-2 Reset Corner on proportional distance to old notes on record in Allegan County Surveyors Office. Set 1/2" Iron & Cap
--	--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 (1/2" iron) 24" Oak N50 deg. E 43.8' 18" Pine N25 Deg. W 52.5' 10" Oak S45 deg. E 49.2' 0' West of center line North and South St. Sign S45 deg. W 35.1'	K-1 (1/2" iron) 36" Oak S5 deg. W 31.5' 18" T Oak S50degE 72.2' 16" Oak N35degE 32.3' 12" Pine N20 deg W 40.1'	K-2 (1/2" Iron) 14" Oak N45°W 18.0' 12" T Oak S30°W 34.5' 6" Ash West 10.0' 9' West of center line Road North & South
--	--	--


SIGNED BY John H. Dillingham DATE September 8, 1983

SURVEYOR'S MICHIGAN REGISTRATION NO. 18927

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_



LIBER 003 PAGE 364

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

Form No. ML 1736

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
DISTRIBUTED BY MICHIGAN SOCIETY OF REGISTERED LAND SURVEYORS