

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan

| (County) | Located in: | Corner Code # |
|------------------------------------|----------------------------|---------------|
| | Casco Township | |
| 1. Public Land Survey | T <u>1</u> N R <u>16</u> W | B-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1994 DEC 16 AM 9:53
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 FILED
 Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

| | | | | | | | | | | | | | |
|----|---|----|----|----|----|----|----|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | | |

I, George J. Mitchell in a field survey on November 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-1

CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY
 NO HISTORY OF CORNER FOUND OR REPORTED BY OTHER SURVEYORS.


APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-11-94
 COUNTY REP. Frank J. Tom Oster

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-1

NO EVIDENCE OF CORNER WAS FOUND. SET CORNER ON INTERSECTION OF TOWNSHIP LINE AND A LINE PRODUCES NORTH FROM SOUTH QUARTER POST THRU THE CENTER OF THE SECTION. THIS POSITION NOR ESTABLISHED BY THE ORIGINAL GOVERNMENT SURVEY. THIS MONUMENT IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION OF THE CORNER.

MEASURED 3191.96 FEET WEST (PLATTED AS 3192.00 FEET) TO THE NE CORNER OF GLENN SHORES NO. 1 PLAT. MEASURED 2776.23 FEET SOUTH TO RECORD CENTER OF SECTION 6, TOWN 1 NORTH, RANGE 16 WEST.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-1

SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP IN SMALL STONE PILE.
 A.C. remon tag & nail in SE side of 7" Oak AZ. 45° 23.45'
 A.C. remon tag & nail in South side of 9" Ash AZ. 270° 11.93'
 A.C. remon tag & nail in SW side of 6" Oak AZ. 135° 16.59'
 A.C. remon tag & nail in East side of 4" Oak AZ. 210° 31.72'
 Ganges Township Corner B-13 AZ. 270° 93.70'

Signed by George J. Mitchell Date November 4, 1994
 Surveyor's Michigan License No. 19618

FILE # 0005 PAGE 001