

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan (County) Located in: Casco Township Corner Code # B-13

1. Public Land Survey T 1 N 16 W \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds  
 ALLEGAN COUNTY, MICHIGAN  
 George J. Mitchell  
 1995 DEC 14 PM 2:32

FILED

**SURVEY & REMONUMENTATION**  
**APR 29 1996**  
**COMMISSION**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George J. Mitchell, in a field survey on November 15, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: B-13

SEE SHEET 2 OF 2



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13  
 FOUND 5/8" REBAR OVER STONE ON TOWNLIN FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 MEASURED 2636.14 FEET EAST TO C-13  
 THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 14, 1995

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 11-14-95  
 COUNTY REP. André Van Orden

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 REPLACED REBAR AND STONE WITH 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.  
 A.C. remon tag & nail in SE side of Power Pole AZ. 60° 78.01'  
 A.C. remon tag & nail in NE side of 16" Cherry AZ. 125° 84.79'  
 A.C. remon tag & nail in West side of 18" Cherry AZ. 180° 83.64'  
 A.C. remon tag & nail in SE side of 8" Maple AZ. 250 87.53'  
 Centerline of Asphalt pavement AZ. 180° 2.0'

SHEET 1 OF 2

Signed by George J. Mitchell Date November 15, 1995  
 Surveyor's Michigan License No. 19018

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN. 1982

0005 PAGE 190

1 OF 2

## GOVERNMENT CORNER HISTORY

SOUTH QUARTER POST OF SECTION 31  
TOWN 1 NORTH, RANGE 16 WEST, CASCO TOWNSHIP

B-13

1831 L. LYON	SET POST @ 40.00 CHAINS 30" HEMLOCK N62E 23 LKS 10" BEECH N32W 14 LKS	
OLD COUNTY SURVEYOR	SET STONE 10" MAPLE S71W 16 LKS 14" MAPLE S40E 44 LKS	
RATEKIN WIT CARD 1969	FD REMAINS OF 4" STAKE WITH STONE SET 3/4" IRON	CHECK 1995
MITCHELL 1977 LCRC L3, P154	FD 5/8" REBAR POWER POLE NE 78.13' 10" CHERRY SSE 51.84' TELE CABLE BOX SW 33.85' CL ROAD SOUTH 2.0'	CHECK 1995 CHECK 1995 CHECK 1995 CHECK 1995 CHECK 1995
MITCHELL 1995	FD 5/8" IRON BAR OVER STONE	