

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION For corners in Allegan

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for (County), Located In: Casco Township, Corner Code: C-1, and various survey types (Public Land Survey, Property Controlling, etc.)

1994 DEC 16 AM 9:53 REGISTER OF DEEDS ALLEGAN COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

Grid table with columns A-M and rows 2-13, used for recording corner locations.

I, George J. Mitchell, in a field survey on November 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1
L. LYON SET POST 1831 MDOT 1969
NORTH BETWEEN SEC. 5 & 6 SET CONG. MON WITH 1/2 IRON ROD
82.6 CH'S TO TOWN LINE 137 LKS 18" MAPLE N80W 60.60'
EAST OF CORNER. 37" CHERRY N85E 21.29'
GANGES TWP. CORNER WEST 90.84'

RATEKIN CARD FILE - SAME AS MDOT MITCHELL 1972 - SAME AS MDOT
B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1
FOUND CONCRETE MONUMENT 3.08 FEET NORTH OF TOWNLINE. SET CORNER ON TOWNLINE DUE SOUTH OF CONCRETE MONUMENT 3.08 FEET AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

MEASURED 2625.81 FEET WEST TO B-1 & MEASURED 2621.81 FEET EAST TO D-1.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-11-94
COUNTY REP. Rick L. Van Orden



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1
SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.
1/2" Iron in Concrete Monument
A.C. remon tag & nail in South side of 32" Cherry AZ. 00° 3.08'
A.C. remon tag & nail in South side of 7" Ash AZ. 80° 20.66'
A.C. remon tag & nail in SE side of 6" Ash AZ. 280° 15.70'
Ganges Township Corner C-13 AZ. 40° 9.20'
AZ. 270° 90.81'

Signed by George J. Mitchell Date November 4, 1994
Surveyor's Michigan License No. 19618

LIBR. 0005 PAGE 002