

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan (County) Located In: Casco Township Corner Code # C-13

1. Public Land Survey T 1 N R 16 W _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling _____
 in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous _____
 Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1995 DEC 14 PM 2:32
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 FILED

Register of Deeds Stamp & File Number

**SURVEY &
 REMONUMENTATION
 APR 29 1996
 COMMISSION**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, George J. Mitchell in a field survey on November 15, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
 manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
 Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
 as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-13

SEE SHEET 2 OF 2



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13
 FOUND RAIL ROAD SPIKE OVER STONE ON TOWNLINE FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

MEASURED 2627.12 FEET EAST TO D-13
 MEASURED 2636.14 FEET WEST TO B-13

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 14, 1995

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-14-95
 COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13
 REPLACED R.R.SPIKE AND STONE WITH 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.
 A.C. remon tag & nail in NW side of Power Pole AZ. 22° 78.10'
 A.C. remon tag & nail in NE side of Power Pole AZ. 145° 26.53'
 A.C. remon tag & nail in NW side of 28" Ash AZ. 240° 47.75'
 A.C. remon tag & nail in East side of 10" Quad Maple AZ. 325° 118.70'
 Geneva township Corner C-1 AZ. 90° 260.20'

SHEET 1 OF 2

Signed by George J. Mitchell Date November 15, 1995
 Surveyor's Michigan License No. 19618

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1973
 REVISED JAN., 1983

1552 0005 PAGE 192

1 OF 2

GOVERNMENT CORNER HISTORY

SOUTHEAST CORNER OF SECTION 31
TOWN 1 NORTH, RANGE 16 WEST, CASCO TOWNSHIP

C-13

1831 L. LYON

WEST ON SOUTH SIDE OF SECTION 32
40.00 CHAINS SET POST LKS
75.88 INTERSECT WEST BOUNDARY 283 LKS NORTH OF
TEMP. POST & SET CORNER FOR T'S 16 & 17 WEST.
80.00 CHAINS SET POST FRO 31 & 32
JOG 271.92 FEET

GARDNER 1896

SET STAKE & STONE
16" MAPLE N60E 56 LKS
14" HEMLOCK N48W 40 LKS
2625' EAST TO S1/4 POST SEC 32
2627.10 MEASURED 1995 TO S1/4 POST SEC 32.
2636.14 MEASURED 1995 TO S1/4 POST SEC 31

MITCHELL 1977
LORC L3, P154

FD RAIL ROAD SPIKE			CHECK 1995
POWER POLE	NE	78.30'	CHECK 1995
POWER POLE	SE	26.60'	CHECK 1995
TELE POLE	SW	58.27	CHECK 1995

MITCHELL 1985

SAME AS ABOVE

MITCHELL 1995

FD RAIL ROAD SPIKE OVER STONE
GENEVA TWP., CORNER EAST 260.20'