

REMONUMENTATION

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION

For corners in
Allegan

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

	Located In:	Comer Code #
	Casco Township	
1. Public Land Survey	T 1 N R 16 W	D-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

1994 DEC 16 AM 9:53
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 REGISTER OF DEEDS STAMP & FILE NUMBER
 FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George J. Mitchell, in a field survey on November 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
D-1
 CORNER WAS NOT SET IN ORIGINAL GOVERNMENT SURVEY


1906 OLD COUNTY SURVEYOR NOTES	RATEKIN CARD FILE	MDOT EBERT 1969
"FENCE POST"	CONCRETE MON WITH 1/2" IR. ROD.	CONC MON WITH 1/2" IR
2622' WEST TO NW CORNER	17" ASH WEST 58.83'	17" ASH W. 58.83'
2792 SOUTH TO CENTER	4" BASSWOOD N35E 3.87'	5" OAK N35E 3.87'
	GANGES COR WEST 78.29'	6" OAK N24E 26.58'
RATEKIN CARD FILE - SAME AS MDOT	MITCHELL 1978 - SAME AS MDOT	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1
 FOUND CONCRETE MONUMENT ON TOWNLINE FROM ABOVE WITNESSES. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEY. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.

MEASURED 2621.81 FEET WEST TO C-1

APPROVED REMONUMENTATION CORNER
 P.A. 343 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 12-11-94
 COUNTY REP. [Signature]



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1
 REMOVED CONCRETE MONUMENT AND SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. remon tag & nail in West side of 15" Oak	AZ. 25°	39.17'
A.C. remon tag & nail in North side of 6" Maple	AZ. 90°	30.26'
A.C. remon tag & nail in West side of 10" Oak	AZ. 180°	6.93'
A.C. remon tag & nail in South side of 19" Oak	AZ. 280°	52.15'
Ganges Township Corner D-13	AZ. 270°	78.23'

Signed by George J. Mitchell
 Surveyor's Michigan License No. 19618

Date December 12, 1994

LIEP: 0005 PAGE 003