

**SURVEY & REMONUMENTATION**

7-2-

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

**SECTION**  
For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

ALLEGAN COUNTY..... Located in: ..CASCO..... Township  
Corner Code #

1. Public Land Survey T. 1 N., R. 16 W., D-13.....  
T..... R..... S1/4 POST, SEC 32
2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....
4. Lot No. ...., Recorded Plat .....
5. Private Claims.....

98 JAN 21 PM 1:18  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.  
*James L. ...*

FILED

I, Donald R. Pitts Jr., in a filed survey on June 5, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13

SEE SHEET 2 OF 2 FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13

FOUND 1/2" REBAR IN MONUMENT BOX.

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 10-14-97  
 COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13

SOUTH QUARTER POST OF SECTION 32, TOWN 1 NORTH, RANGE 16 WEST

FOUND 1/2" REBAR IN MONUMENT BOX FROM CORNER HISTORY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON OCTOBER 14, 1997


SET ALLEGAN COUNTY STANDARD 3/4" BY 24" IRON PIN WITH REMON CAP IN MONUMENT BOX.

- |   |     |      |              |
|---|-----|------|--------------|
| A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF POWER POLE           | AZ. | 240° | 68.46 FEET   |
| NORTHEAST CORNER OF CEMENT BLOCK SINGLE STORY HOUSE             | AZ. | 150° | 61.30 FEET   |
| SOUTHWEST CORNER OF CEMENT BLOCK SINGLE STORY HOUSE             | AZ. | 175° | 69.01 FEET   |
| NORTHWEST CORNER OF CEMENT BLOCK SINGLE STORY HOUSE             | AZ. | 190° | 49.32 FEET   |
| B-I, T1S, R16W, - REBAR IN MON BOX, 1.04 FEET NORTH OF BASELINE | AZ. | 272° | 105.38 FEET  |
| CORNER D-13 TO C-13 MEASURED                                    |     |      | 2627.12 FEET |
| CORNER D-13 TO E-13 MEASURED                                    |     |      | 2628.67 FEET |

Signed by Donald R. Pitts Jr. Date 17 Nov 1997

Surveyor's Michigan License No. 25867

SHEET 1 OF 2



LIBER 0006 PAGE 021

GOVERNMENT CORNER HISTORY  
SOUTH QUARTER POST OF SECTION 32  
TOWN 1 NORTH, RANGE 16 WEST

D-13

L.LYON 1831	WEST ON SOUTH SIDE OF SEC 32 40.00 CH SET QUARTER SECTION POST ELM 10 N7E 19 BEECH 10 N34W38
GARDNER 1895	SET STAKE AND STONE MAPLE 12" SE 43.2 MAPLE 12" SW 29.0 2625 FEET TO SOUTHWEST CORNER
MITCHELL 1977	FD PIPE & MEASURED 2627.38 FROM C-13 TO D-13
MITCHELL 1994	REPLACED PIPE WITH 1/2" REBAR IN MON. BOX FOR VAN BUREN COUNTY ROAD PROJECT.
MITCHELL 1995	MEASURED 2627.12 FEET FROM C-13 TO D-13 AS SHOWN ON L.C.R.C. RECORDED LIBER 5, PAGE 192.
PITTS 1997	FD. 1/2" REBAR IN MON. BOX MEA. 2627.12 FEET D-13 TO C-13 MEA. 2628.67 FEET D-13 TO E-13