

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
 ALLEGAN COUNTY..... Located in: ..CASCO..... Township  
 Corner Code #

1. Public Land Survey T. 1 N. R. 16 W. E-1.....
2. Property Controlling S..... T..... R..... NE COR. SEC. 5  
 in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....  
 Property in Sec. S..... T..... R.....
4. Lot No. ...., Recorded Plat .....
5. Private Claims.....

97 JAN 22 PM 1:14  
 FILED  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 Register of Deeds Stamp & File Number

I, .... George J. Mitchell....., in a filed survey on ...10/15/1995 & 10/29/96..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1

SEE SHEET 2 OF 2 FOR CORNER HISTORY



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1

FOUND DRAG HANDLE 0.45 FEET SOUTH OF THE TOWNLINE. SET CORNER ON TOWNLINE AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 14, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1

SET ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP.

APPROVED REMONUMENTATION CORNER  
 P.A. 343 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 11-14-95  
 COUNTY REP. [Signature]

A.C. REMON TAG & NAIL IN WEST SIDE OF POWER POLE	AZ.	167°	73.60 FEET
A.C. REMON TAG & NAIL IN WEST SIDE OF 18" MAPLE	AZ.	00°	53.95 FEET
A.C. REMON TAG & NAIL IN SOUTH SIDE OF 18" OAK	AZ.	275°	82.80 FEET
SOUTH FACE OF 8" CEDAR TREE	AZ.	45°	2.25 FEET
GANGES TOWNSHIP CORNER	AZ.	270°	63.05 FEET

Signed by George J. Mitchell Date November 12, 1996

Surveyor's Michigan License No. ....19618.....

SHEET 1 OF 2

NORTHEAST CORNER OF SECTION 5  
TOWN 1 NORTH, RANGE 16 WEST, CASCO TOWNSHIP

E-1

ORIG. GOVERNMENT NORTH BETWEEN SECTIONS 4 & 5  
SET POST @ 40.00 CHAINS  
82.61 CHAINS TO N. BOUNDARY 95 LKS EAST OF POST  
SET POST FOR SECTIONS 4 & 5  
BEECH 22 S61W 24LKS  
HEMLOCK 8 S50E 29LKS

D. RATEKIN (WITNESS CARDS) FD DRAG HANDLE & WOOD STAKES 1969  
POWER POLE SSE 73.2  
POWER POLE N 86.9'  
JOB DISTANCE 63.0' OR 69.94'

L.C.R.C. MDOT 1972 FD WOOD STAKE & 1 1/4" IRON BAR (DRAG HANDLE)  
INTERSECTION OF E. LINE SECTION 5 & S. LINE SEC. 33  
GANGES TWP = 2.18 NORTH  
18" CHERRY N75W 83.18  
9" POPLAR WEST 54.76  
P. POLE #1083 S13E 73.17  
CL RD WEST 27.1

MITCHEL 1995 FD DRAG HANDLE  
CENTER/ROAD WEST 27'  
18" OAK N75W 82.8'  
GANGES CORNER WEST 63.05'  
P. POLE S13E 73.17'