

MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE

60 FEB -1 AM 8:36

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY Located in: ..CASCO.. Township Corner Code #

- 1. Public Land Survey T.1 N.. R.16 W.E-9..... T..... R..... NE CORNER, SECTION 29
2. Property Controlling S..... T..... R..... in Section S..... T..... R.....
3. Miscellaneous S..... T..... R..... Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

Joyce Little

REGISTER OF DEEDS ALLEGAN COUNTY

Register of Deeds Stamp & File Number

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column D and row 9.

I, George J. Mitchell P.S....., in a field survey on ...May 25, 1999..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

- A. Description of original monument and accessories and/or subsequent restoration:
1. C. BRITAIN D.S. 1831 - SET POST - HEMLOCK 40 - S47E, 19 LKS & HEMLOCK 20 - N76W, 31 LKS
2. T.O. WILLIAMS CO. SUR. 1890 - STONE
3. MACDOUGALL (NO DATE) - STONE & IRON
4. D. RATEKIN CO. SUR. 1971 - L.C.R.C. L.1, P. 20 - 3/4" IRON & STONE - STREET SIGN - ESE, 15.3' & 20' MAPLE - ENE, 23.9' AND 8" TWIN MAPLE- SE, 34.9'
5. P. VANKOOTEN P.S. 1973 - L.C.R.C. L. 2. P. 115 - 5/8" IRON IN MON BOX - 24" MAPLE- SSE, 56.42' & 14" SPRUCE- WNW, 70.58' AND 18" MAPLE- NW, 53.68' & DISRANCE OF 2637.20' SOUTH TO E-10.
6. G. MITCHELL P.S. 1978 - FD 5/8" IRON IN MON BOX - 20" MAPLE- ENE, 53.0' & 30" MAPLE- EAST, 23.7' & 18" TWIN MAPLE - SE, 35.0' & 2637.7' SOUTH TO E-10
7. R. MOORED P.S. 1998 - FD 3/4" IRON IN MON BOX - STREET SIGN- S75E, 15.3' & 20" MAPLE- EAST, 23.0' & 8" TWIN MAPLE- S45E, 34.9' AND SE CORNER OF HOUSE- N45W, 103.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.
FOUND 5/8" REBAR IN CONCRETE IN MONUMENT BOX FROM ITEMS 4 THRU 7 OF ABOVE CORNER HISTORY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
GLUED A ALLEGAN COUNTY REMON CAP ON TOP OF 5/8" REBAR IN MONUMENT BOX.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON JUNE 8, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
NORTHEAST CORNER OF SECTION 29, TOWN 1 NORTH, RANGE 16 WEST.

Table with 4 columns: Description, AZ, Angle, Feet. Rows include A.C. REMON TAG & NAIL IN NORTH SIDE OF 10" PINE, A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 16" MAPLE, A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 36" MAPLE, A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 24" PINE.

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED JUNE 8, 1999 COUNTY REP. [Signature]

Signed by [Signature] Date 10/28/99

Surveyor's Michigan License No.19618.....

