

MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY Located in: ..CASCO.. Township Corner Code #

- 1. Public Land Survey T.1 N.. R.16 W.E-12..... T..... R..... E1/4 POST, SECTION 32
2. Property Controlling S..... T..... R..... in Section S..... T..... R.....
3. Miscellaneous S..... T..... R..... Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

REGISTER OF DEEDS ALLEGAN COUNTY JUNE 8, 1999

I, George J. Mitchell P.S....., in a field survey on ...May 25, 1999..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column C and row 12.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. C. BRITAIN D.S. 1831 - SET POST AT 40 CHAINS - MAPLE 30 - S72E, 15 LKS & BEECH 10 - N74W, 11LKS
2. MACDOUGALL (NO DATE) - STAKE & STONE
3. D. RATEKIN P.S. 1971 L.C.R.C. L. 1, P. 23 - USED ROAD GRADER TO SEARCH AREA - FOUND NOTHING - SET CORNER BY SINGLE PROPORATION - SET CORNER BY MEASURING 2634.29 FEET FROM CORNER TO THE NORTH AND SOUTH - SET 1" IRON - 30" MAPLE - WEST, 21.35' & POWER POLE - N85W, 46.3' & T.C.B. - N25W, 53.8' AND 16" WHITEWOOD - N30E, 75.0'
4. E. STEFEN P.S. 1975 - FD 1" IRON - MEAS. 2634.3' SOUTH TO CORNER ON BASELINE.
5. G. MITCHELL P.S. 1988 - FD 1" IRON - 8" ELM - N30E, 41.73' & 20" MAPLE - N20W, 64.03' & POWER POLE - N80W, 46.54' AND IRON - WEST, 33.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON FROM ITEMS 3 AND 5 OF ABOVE CORNER HISTORY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

SET ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON JUNE 8, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

EAST QUARTER POST OF SECTION 32, TOWN 1 NORTH, RANGE 16 WEST.

- A.C. REMON TAG & NAIL IN NORTH SIDE OF POWER POLE AZ. 275° 46.40 FEET
A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 28" TULIP AZ. 040° 75.45 FEET
A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 8" POPLAR AZ. 085° 43.55 FEET
A.C. REMON TAG & NAIL IN T.C.B. MARKER POST AZ. 240° 36.00 FEET

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED JUNE 8, 1999 COUNTY REP. [Signature]

Signed by: [Signature] Date: 10/28/99

Surveyor's Michigan License No.19618.....

