

SURVEY & REMONUMENTATION

APR 07 1998

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN COUNTY..... Located in: CASCO..... Township
Corner Code #

1. Public Land Survey T.1 N. R.16 W. E-13.....
2. Property Controlling S..... T..... R..... SE CORNER, SEC 32
3. Miscellaneous S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

98 JAN 21 PM 1:18
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
James D. ...

FILED

I, Donald R. Pitts Jr., in a filed survey on June 5, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
E-13

SEE SHEET 2 OF 2 FOR CORNER HISTORY

| | | | | | | | | | | | | |
|----|---|---|---|---|---|---|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | | | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | | | | | | | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | | | | | | | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | | | | | | | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | | | | | | | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | | | | | | | | | | | | |
| 13 | | | | | | | | | | | | |

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-13
FOUND 1/2" REBAR IN MONUMENT BOX.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-13
SOUTHEAST CORNER OF SECTION 32, TOWN 1 NORTH, RANGE 16 WEST.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-14-97
COUNTY REP. K.V.O.


FOUND 1/2" REBAR IN MONUMENT BOX FROM CORNER HISTORY. AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON OCTOBER 14, 1997
SET ALLEGAN COUNTY STANDARD 3/4" BY 24" IRON PIN WITH REMON CAP IN MONUMENT BOX.

| | | | |
|---|-----|------|--------------|
| A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF POWER POLE | AZ. | 285° | 75.04 FEET |
| A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF POWER POLE | AZ. | 230° | 97.92 FEET |
| A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 12" CHERRY | AZ. | 070° | 89.55 FEET |
| TOP CENTER OF TELEPHONE CABLE BOX | AZ. | 225° | 49.13 FEET |
| C-1, T1S, R16W, - REBAR IN MON BOX. 2.13 FEET NORTH OF BASELINE | AZ. | 272° | 104.64 FEET |
| CORNER E-13 TO D-13 MEASURED | | | 2628.67 FEET |
| CORNER E-13 TO F-13 MEASURED | | | 2633.01 FEET |

Signed by Donald R. Pitts Jr. Date 17 Nov 1997
Surveyor's Michigan License No. 25867

SHEET 1 OF 2



GOVERNMENT CORNER HISTORY

SOUTHEAST CORNER OF SECTION 32
TOWN 1 NORTH, RANGE 16 WEST

E13

L.LYON 1831 SET POST FOR CORNER OF SECTIONS 32 & 33
SYCAMORE 28 N66-1/3E 17
BEECH 13 N41-1/2W 25

GARDNER 1895 SET STAKE AND STONE
MAPLE 19" SE 54.8 FEET
MAPLE 12" SOUTH 23.0 FEET
2625 FEET TO SOUTH QUARTER POST

D.A. RATEKIN 1971 FOUND STONE & OLD STAKE "1971"
SET LARGE BOAT SPIKE OVER STONE
ST. SIGN N40W 38.2' (GONE)
T.C. BOX S25W 15.6'
34" MAPLE SOUTH 22.6' (GONE)
30" MAPLE S70E 54.5' (GONE)
9" ASH N60W 102' (GONE)

D.A. RATEKIN 1971 L.C.R.C. LIBER 1, PAGE 19
STONE WITH LARGE BOLT OVER
SAME WITNESSES AS ABOVE EXCEPT ASH

MITCHEL 1992 FOUND BOAT SPIKE
34" MAPLE SOUTH 22.6' (GONE)
30" MAPLE S70E 54.5' (GONE)
T.C.BOX S25W 15.6'

MITCHELL 1994 REPLACED CORNER WITH 1/2" REBAR IN MON BOX
FOR V.B. CO. ROAD COMM. PROJECT

PITTS 1997 FOUND 1/2" REBAR IN MON BOX
VAN BUREN CORNER - WEST 104.64'