

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: ..CASCO..... Township
Corner Code #

1. Public Land Survey T.1 N., R.16 W. F-1.....
T..... R..... N1/4 POST, SEC. 4
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

REGISTER OF DEEDS
 ALLEGAN COUNTY
 97 JAN 22 PM 1:14
 FILED
 Register of Deeds Stamp & File Number

I, George J. Mitchell....., in a filed survey on ...OCTOBER 29, 1996..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1

NOT SET BY GLO
SEE SHEET 2 OF 2 FOR CORNER HISTORY

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-12-96
COUNTY REP. [Signature]



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1

FOUND PINCH PIPE ON TOWNLINE FROM CORNER HISTORY AND ACCEPTED ITS LOCATION. THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER.
THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMBER 12, 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1

REPLACED PINCH PIPE WITH ALLEGAN COUNTY STANDARD 3/4" BY 36" IRON PIN WITH REMON CAP.

A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 8" ELM	AZ.	25°	15.95 FEET
A.C. REMON TAG & NAIL IN WEST SIDE OF POWER POLE	AZ.	180°	54.90 FEET
A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 8" ELM	AZ.	280°	12.80 FEET
A.C. REMON TAG & NAIL IN WEST SIDE OF 12" ELM	AZ.	355°	40.25 FEET
GANGES TOWNSHIP CORNER	AZ.	270°	52.04 FEET

Signed by [Signature] Date November 15, 1996

Surveyor's Michigan License No.19618.....

SHEET 1 OF 2

LIBER 0005 PAGE 350

GOVERNMENT CORNER HISTORY

NORTH QUARTER POST OF SECTION 4
TOWN 1 NORTH, RANGE 16 WEST

F-1

ORIG. GOVERNMENT	NOT SET JOG ON EAST SEC LINE - 63 LKS WEST (41.58) JOG ON WEST SEC LINE - 95 LKS WEST (62.70)
MITCHELL 12/28/78	FD PINCH PIPE POWER POLE SOUTH 54.7' GANGES COR. WEST 52.0' MEAS. 2633.59 EAST TO NE CORNER
TRI COUNTY 9/10/86	SURVEY IN NE1/4 SHOWS CORNER, NO WITNESSES 2633.60 EAST TO NE CORNER
MITCHELL 10/26/88	FROM SURVEY IN SEC 33, GANGES FD PINCH PIPE 52.00 FT EAST OF GANGES CORNER CORNER IN CENTER OF DITCH TO SOUTH 2633.79 EAST TO NE CORNER
MITCHELL 5/29/95	FD PINCH PIPE PIPE WEST 52.00 FT. P.P. SOUTH 54.8 6" ASH EAST 41.0 6" ASH WNW 13.0 2633.80 EAST TO NE CORNER
MITCHELL 10/96	FOUND PINCH PIPE MEAS 2633.84 EAST TO NE CORENR CORNER FD TO BE 0.06' NORTH OF TOWNLINE