

SECTION
 11189101

**ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

.....ALLEGAN Located in: **.CASCO..... Township**
 Corner Code #

1/28/1999 2:44:39 PM

JOYCE A. WATTS
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH

1. Public Land Survey T..1..N R..16 WG-1.....
 T..... R..... NW COR, SEC 3
2. Property Controlling S..... T..... R.....
 in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
 Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

Register of Deeds Stamp & File Number

LIBRO 006 PAGE 38

I, **George J. Mitchell**....., in a filed survey on **10/26 thru 11/11/98**.....
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner
 points mentioned in lines 1 and 2 above were in conformance with regulations and rules
 therefore as required in the current manual of survey instructions of the United States
 Department of the Interior, Bureau of Land Management or by decree of a Court of Law
 and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance
 with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law;
 established, re-established, monumented, re-monumented, recovered, found as expressed
 below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				3						
3												
4	7	9	9			10			11			12
5												
6	14	17	16			15			14			13
7												
8	19	20	21			22			21			24
9												
10	30	28	28			27			26			25
11												
12	31	32	33			34			35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-1) CALVIN BRITAIN 1831, INTERSECTED TOWN LINE 63 LKS EAST
 OF PAST AND SET POST BEECH 10 N45W 17, SUGAR 12 N77E 50

COUNTY SURVEYORS RECORDS (NO DATE) FD IRON P. POLE SE 71.8'
 ON SLOPE OF RD SHOULDER GANGES COR WEST 41.58' C/L RD WEST 19.8'

G. MITCHELL 1994 FD 1-1/4" IRON 4" MAPLE SSE 28.9'
 POWER POLE SE 72.6' C/L ROAD WEST 21.7'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED Nov. 10, 1998
 COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1) FOUND 1-1/4" IRON BAR 1.79 FEET SOUTH OF THE TOWNLINE FROM CORNER HISTORY AND IS
 ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL
 CORNER

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1) NORTHWEST CORNER OF SECTION 3, TOWN 1 NORTH, RANGE 16 WEST
 SET SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP 1.79 FEET NORTH OF FD IRON BAR

A.C. REMON TAG & NAIL IN SW. SIDE OF 36" WALNUT	AZ.	205°	207.19 FEET
A.C. REMON TAG & NAIL IN S. SIDE OF 14" TWIN BOX ELDER	AZ.	272°	70.07 FEET
A.C. REMON TAG & NAIL IN SW SIDE OF POWER POLE	AZ	165°	72.71 FEET
CENTERLINE OF 66TH STREET	AZ	270°	20.5' FEET
1-1/4" IRON BAR	AZ	180°	1.79 FEET
GANGES TOWNSHIP CORNER	AZ	270°	41.50 FEET
MEASURED G-1 TO H-1			2646.39 FEET

Signed by *George J. Mitchell* Date Nov. 12, 1998
 Surveyor's Michigan License No.19618.....

