

**SURVEY &
REMONUMENTATION**

APR 07 1998

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN COUNTY..... Located in: ..CASCO..... Township
Corner Code #

- 1. Public Land Survey T. 1 N. R. 16 W. G-13.....
- 2. Property Controlling S..... T..... R..... SE CORNER, SEC. 33
in Section S..... T..... R.....
- 3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
- 4. Lot No., Recorded Plat
- 5. Private Claims.....

98 JAN 21 PM 1:18
 REGISTER OF RECORDS
 ALLEGAN COUNTY
James A. [Signature]

FILED

I, **Donald R. Pitts Jr.**, in a filed survey on **June 5, 1997**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13

SEE SHEET 2 OF 2 FOR CORNER HISTORY

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
5												
6												
7												
8												
9												
10												
11												
12												
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13

FOUND 1/2" REBAR IN MONUMENT BOX

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 10-14-97
 COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13

SOUTHEAST CORNER OF SECTION 33, TOWN 1 NORTH, RANGE 16 WEST

FOUND 1/2" REBAR IN MONUMENT BOX FROM CORNER HISTORY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON OCTOBER 14, 1997.


SET ALLEGAN COUNTY STANDARD 3/4" BY 24" IRON PIN WITH REMON CAP IN MONUMENT BOX.

- | | | | |
|---|-----|------|------------|
| A.C. REMON TAG & NAIL IN WEST SIDE OF 16" PINE | AZ. | 175° | 33.12 FEET |
| A.C. REMON TAG & NAIL IN NORTHWEST SIDE OF 12" BLUE SPRUCE | AZ. | 045° | 44.85 FEET |
| SOUTHEAST CORNER OF TELEPHE CABLE BOX AT GROUND | AZ. | 225° | 44.70 FEET |
| CENTER OF TELEPHONE CABLE BOX AT TOP | AZ. | 290° | 68.50 FEET |
| E-1. T1S, R16W. - REBAR IN MON BOX. - 0.89' SOUTH OF BASELINE | AZ. | 270° | 89.93 FEET |
| CORNER G-13 TO F-13 MEASURED 2635.28 FEET | | | |
| CORNER G-13 TO H-13 MEASURED 2636.43 FEET | | | |

Signed by *Donald R. Pitts Jr.* Date 17 Nov 1997

Surveyor's Michigan License No. 25867

SHEET 1 OF 2



0006 PAGE 027

GOVERNMENT CORNER HISTORY
 SOUTHEAST CORNER OF SECTION 33
 TOWN 1 NORTH, RANGE 16 WEST

G-13

L.LYON 1831

SET POST FOR CORNERS SECTION 33 & 34
 HEMLOCK 20 N75-1/2E 39
 BEECH 7 N58-1/4W 24

GARDNER 1895

SET IRON
 NO WITNESSES

COUNTY SURVEYOR NOTES

1/2" IRON
 SE CORNER TELE OUTLET S45W 45.0'
 ST. SIGN N60W 69.54' (GONE)
 10" BLUE SPRUCE N45E 44.8'
 10" PINE S05E 33.0'

CO. ROAD COMMISSION

MULTIPLE BOX ELDER SE 73.14' (GONE)
 26" MAPLE SW 85.8' (GONE)
 TEL. POLE NE 62.85'
 T.C. BOX NW 66.86'
 12" ELM N59E 46.3'
 28" W. ASH N13W 137.5'
 90' WEST TO NW COR SEC 4 VAN BUREN CO.

CONSUMERS POWER

FD. 2" IRON
 SAME WITNESSES AS COUNTY SURVEYOR
 NOTE: DIS. G-13 TO H-13 MEAS. 2636.19'
 1997 MEASUREMENT - 2636.43'

MITCHELL 1993

FOUND 1/2" REBAR IN MON BOX
 POWER POLE N40E 55.14'
 16" PINE S05E 33.12'
 T.C. BOX S50W 44.53'
 T.C. BOX N70W 68.00'

PITTS 1997

FOUND 1/2" REBAR IN MON BOX
 VAN BUREN CORNER - WEST 89.93'
 G13 TO F13 - 2635.28'
 G13 TO H13 - 2636.43'