

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

.....ALLEGAN..... Located in: .CASCO..... Township
Corner Code #

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

1. Public Land Survey T..1.N R..16 WH-1.....
T..... R..... N1/4 POST, SEC 3
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

Register of Deeds Stamp & File Number

I, **George J. Mitchell**....., in a filed survey on ...10/26 thru 11/11/98..... do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	0	1	2	3	4	5	6	7	8	9	10	11
3												
4	7	8	9	10	11	12	13	14	15	16	17	18
5												
6	19	20	21	22	23	24	25	26	27	28	29	30
7												
8	31	32	33	34	35	36	37	38	39	40	41	42
9												
10	43	44	45	46	47	48	49	50	51	52	53	54
11												
12	55	56	57	58	59	60	61	62	63	64	65	66
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-1) NOT SET IN ORIGINAL GOVERNMENT SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1) FOUND 1 IRON BAR 0.62 FEET SOUTH OF THE TOWNLINE FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND FAITHFUL DETERMINATION OF THE POSITION OF THE CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1) NORTH QUARTER POST OF SECTION 3, TOWN 1 NORTH, RANGE 16 WEST

SET SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP 0.62 FEET NORTH OF FD IRON BAR

A.C. REMON TAG & NAIL IN S. SIDE OF 10" MAPLE	AZ.	090°	24.30 FEET
A.C. REMON TAG & NAIL IN S. SIDE OF 30" OAK	AZ.	275°	10.35 FEET
A.C. REMON TAG & NAIL IN SW SIDE OF POWER POLE	AZ.	220°	54.27 FEET
A.C. REMON TAG & NAIL IN SW SIDE OF 20" OAK	AZ.	340°	35.45 FEET
GANGES TOWNSHIP CORNER	AZ.	270°	57.00 FEET
1" IRON BAR	AZ.	180°	0.62 FEET
MEASURED H-1 TO G-1			2646.39 FEET
MAASURED H-1 TO I-1			2646.47 FEET

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED Nov. 10, 1998
COUNTY REP. [Signature]

Signed by George J. Mitchell Date Nov. 17, 1998
Surveyor's Michigan License No.19618.....



LIBERO 006 PAGE 39