

SURVEY & REMONUMENTATION

APR 07 1998

9-2-

SECTION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ALLEGAN COUNTY..... Located in: ..CASCO..... Township
Corner Code #

- 1. Public Land Survey T.1 N., R.16 W.H-13.....
T..... R..... S1/4 POST SEC. 34
- 2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
- 3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
- 4. Lot No., Recorded Plat
- 5. Private Claims.....

98 JAN 21 PM 1:18
 REGISTER OF RECORDS
 ALLEGAN COUNTY MI
 [Signature]
FILED

I, **Donald R. Pitts Jr.**..... in a filed survey on **June 5, 1997**.....
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13

SEE SHEET 2 OF 2 FOR CORNER HISTORY

A	B	C	D	E	F	G	H	I	J	K	L	M
2												
3												
4												
6												
8												
10												
11												
12												
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13

FOUND 1/2" REBAR

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 10-14-97
COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13

SOUTH QUARTER POST OF SECTION 34, TOWN 1 NORTH, RANGE 16 WEST

FOUND 1/2" REBAR FROM CORNER HISTORY, AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON OCTOBER 14, 1997


SET ALLEGAN COUNTY STANDARD 3/4" BY 24" IRON PIN WITH REMON CAP IN MONUMENT BOX.

- A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 36" PINE AZ. 330° 61.09 FEET
- A.C. REMON TAG & NAIL IN SOUTHEAST SIDE OF 16" WILLOW AZ. 020° 49.12 FEET
- SOUTHEAST CORNER OF HOUSE AZ. 340° 107.66 FEET
- A.C. REMON TAG & NAIL IN NORTHEAST SIDE OF 18" PINE AZ. 310° 78.43 FEET
- F-1, T1S, R16W, - 1/2" IRON 0.08' SOUTH OF BASELINE AZ. 270° 84.27 FEET
- CORNER H-13 TO G-13 MEASURED 2636.43 FEET
- CORNER H-13 TO I-13 MEASURED 2636.18 FEET

Signed by Donald R. Pitts Jr. Date 17 Nov 1997

Surveyor's Michigan License No.25867.....

SHEET 1 OF 2



GOVERNMENT CORNER HISTORY
 SOUTH QUARTER POST OF SECTION 34
 TOWN 1 NORTH, RANGE 16 WEST

H13

L.LYON 1831	SET POST AT 40.00 HEMLOCK 12 N73-1/2E 18 PEPPERAGE 14 N44-3/4W 28
GARDNER 1895	STAKE & STONE NO WITNESSES
COUNTY SURVEYOR NOTES	FD STONE WITH "X" 8" PINE NW 60.27" 6" WILLOW NNE 49.06' SE COR. HSE NW 107.72' 8" PINE WNW 78.05'
CONSUMERS POWER 1968 SURVEY	FOUND STONE WITH "X" - ROAD COMM 1967 SAME WITNESS AS COUNTY SURVEYOR DIST G-13 TO H-13 - 2636.19' 1997 MEASUREMENT - 2636.43' DIST H-13 TO I-13 - 2636.15 1997 MEASUREMENT - 2636.18'
MIDDLETON 1974	L.C.R.C. LIBER 2, PAGE 321 FD CORNER BURIED BY ROAD CONSTRUCTION RESET IRON FROM 1968 CONSUMERS POWER SURVEY SE CORNER OF HOUSE NW 102.50' 10" PINE NW 61.6' TO CENTER PHONE PEDESTAL NORTH 30' TO CENTER GENEVA CORNER WEST 84.26'
MITCHELL 1989	FOUND 1/2" IRON POWER POLE N40E 55.14' 16" PINE S05E 33.12' T.C. BOX S50W 44.53' T.C. BOX N70W 68.00'
MITCHELL 1995	FROM L.C.R.C. LIBER 5, PAGE 194 MEASURED WEST 2636.28 FEET FROM I-13 TO H-13
PITTS 1997	FOUND 1/2" REBAR VAN BUREN CORNER - WEST 84.27' MEASURED FROM H-13 TO G-13 - 2636.43' MEASURED FROM H-13 TO I-13 - 2636.18'