

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

.CASCO..... Township
Located in: Corner Code #

FILED

1/28/1999 2:44:39 PM

1. Public Land Survey T..1.N R..16 WJ-1.....
T..... R..... N1/4 POST, SEC 2
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

I, **George J. Mitchell**....., in a filed survey on **10/26 thru 11/11/98**.....
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner
points mentioned in lines 1 and 2 above were in conformance with regulations and rules
therefore as required in the current manual of survey instructions of the United States
Department of the Interior, Bureau of Land Management or by decree of a Court of Law
and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance
with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law;
established, re-established, monumented, re-monumented, recovered, found as expressed
below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		6		5		4		3		2	
5												
6	16		17		18		15		14		13	
7												
8	16		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-1) NOT SET IN THE ORIGINAL GOVERNMENT SURVEY

D.A. RATEKIN L.C.R.C., L. 2, P.333 SET 1" IRON ON JOG DIST.ANCE OF
58.74' EAST OF S1/4 POST, SEC 35, T2N, R16W. IRON WEST 58.74'
8" CHERRY N60E 11.43' 10" T. CHERRY N. 4.15' P. POLE S5W 54.86'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1) FOUND 1 IRON BAR ON TOWNLINE FROM CORNER HISTORY AND IS ACCEPTED AS A CAREFUL AND
FAITHFUL DETERMINATION OF THE POSITION OF THE CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON NOVEMEBR 10. 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1) NORTH QUARTER POST OF SECTION 23, TOWN 1 NORTH, RANGE 16 WEST

REMOVED 1" IRON AND SET SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP

A.C. REMON TAG & NAIL IN W. SIDE OF 28" TRI CHERRY	AZ.	000°	4.00 FEET
A.C. REMON TAG & NAIL IN W. SIDE OF WOOD FENCE POST	AZ.	180°	1.00 FEET
A.C. REMON TAG & NAIL IN S. SIDE OF 14" ASH	AZ.	090°	13.56 FEET
A.C. REMON TAG & NAIL IN S. SIDE OF 12" CHERRY	AZ.	270°	17.05 FEET
A.C. REMON TAG & NAIL IN WEST SIDE OF POWER POLE	AS	185°	54.10 FEET
GANGES TOWNSHIP CORNER	AZ.	270°	58.78 FEET
MEASURED J-1 TO I-1			2620.09 FEET
MAASURED J-1 TO K-1			2626.00 FEET

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED NOV. 10, 1998
COUNTY REP. [Signature]



Signed by George J. Mitchell
Surveyor's Michigan License No. 19618

Date Nov. 12, 1998

LIBER0006 PAGE 31, 2