

APR 25 1995

ALLEGAN COUNTY REMONUMENTATION

COMMISSION For corners in Allegan (County)

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for Located In: Casco Township, Corner Code: K-1, and numbered items 1-5 for survey details.

1994 DEC 16 AM 9:53 REGISTER OF DEEDS ALLEGAN COUNTY, MICHIGAN FILED Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, used for recording corner locations.

I, George J. Mitchell, a field surveyor on December 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 L. LYON 1831 SET POST 85.5 CH. MACDOUGALL STAKE & BRICK NORTH & 66 LKS EAST OF POST 14" HICKORY NW 22' BEECH 4 S14W 22LKS 14" MAPLE BEECH 8 S74E 14LKS TW PIGHICK NNW 23' MOORED 1992 FD SQ. IRON POST. GANGES COR W. 43.8' 15" PINE WETS 52.04' P. POLE SE 64.5' POWER POLE S35E 56.85' POWER POLE S70E 25.03' POWER POLE S45W 67.19'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 FOUND SQUARE IRON POST 0.70 FEET SOUTH OF TOWNSHIP LINE. SET CORNER ON TOWNSHIP LINE DUE NORTH OF SQUARE POST AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

SQUARE IRON POST WAS LEFT IN PLACE FOR REFERENCE PURPOSES.

APPROVED REMONUMENTATION CORNER P.A. 345 OF 1990 ALLEGAN COUNTY DATE APPROVED 11-29-94 COUNTY REP. [Signature]



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 SET 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP. A.C. remon tag & nail in West side of Power Pole AZ. 145° 25.57' A.C. remon tag & nail in West side of Power Pole AZ. 165° 57.60' A.C. remon tag & nail in SE side of Power Pole AZ. 265° 77.70' A.C. remon tag & nail in SE side of Power Pole AZ. 220° 67.76' Ganges Township Corner K-13 AZ. 270° 43.85' Center of North-South asphalt road AZ. 270° 23.5'

Signed by George J. Mitchell Date December 12, 1994 Surveyor's Michigan License No. 19618

LIBER 0005 PAGE 004