

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

MAR 10 1993
 For corners in
ALLEGAN
 COMMISSION
 (County)

1993 DEC 30 PM 2:45
 Register of Deeds
 ALLEGAN COUNTY, MICH.
 Spencer A. Edinger

FILED

Located In: Corner Code #:

1. Public Land Survey T 1 N 16 W K-2
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, George J. Mitchell, in a field survey on November 16, 1993
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	14	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Notes		L.C.R.C. Recorded in Liber 2, Page 381			
N. 40.00 set 1/4 post		April 21, 1975 iron		April 1992, 1" pipe	
for which a sugar 24"	Utility Pole N39°E	61.12'	Power Pole	NE	61.10'
is post	32" Pine S69°E	68.35'	20" Maple	N30W	72.15'
	2' S & 6' W of CL-CL		20" Maple	N60W	73.98'
			1/2" iron	N50W	100.00'
			1/2" iron	N50W	200.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2
 Found 1" Pipe over pointed stone 18" below road surface and accepted pipe as a careful and faithful perpetuation of the position of the original corner.

Power Pole	NE	61.10'
20" Maple	N65WE	73.90'
Tele Cable Box	SE	53.65'
1/2" iron	N50W	100.00'
1/2" iron	N50W	200.00'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2
 Replace Stone & Pipe with A.C. remonumentation 3/4" Iron & Cap.

A.C. remon tag & nail in North side of 29" Maple	AZ. 295°	73.90'
A.C. remon tag & nail in NW side of Power Pole	AZ. 45°	61.15'
A.C. remon tag & nail in East side of 24" maple	AZ. 335°	72.10'
A.C. remon tag & nail in West side of Power Pole	AZ. 160°	160.66'
1/2" Rebar	AZ. 310°	100.00'
1/2" Rebar	AZ. 310°	200.00'

Signed by George J. Mitchell Date 12-29-93
 Surveyor's Michigan License No. 19618

LIBER 004 PAGE 335