

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMM. For corners in  
Allegan  
(County)

	Located In:	Corner Code #
	1 N 16 W	K-3
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN  
*George J. Mitchell*

1993 DEC 30 PM 2:45

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George J. Mitchell December 16, 1993  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Notes L.C.R.C. Recorded in Liber 2, Page 381  
Henlock 24" S57E 14lks April 21, 1975 iron  
Henlock 12" N75W 18lks Utility Pole NE 71.9'  
5 feet West of CL of Road

April 1992  
R.R. Tie Post SW 58.01'  
R.R. Tie Post NW 36.43'  
Power Pole East 71.10'  
1/2" iron West 43.28'  
1/2" iron West 86.13'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1-1/2" iron bar in monument box and accepted iron as a careful and faithful perpetuation of the position of original corner based on remaining witnesses and measurements north and east.

Power Pole NE 99.0' (to face)  
Tele Pole SW 51.6'  
1/2" iron West 43.28'  
1/2" iron West 86.19'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set A.C. remonumentation 3/4" Iron & Cap 6" below gravel surface  
A.C. remon tag & nail in East side of 29" Pine AZ. 165° 190.79'  
A.C. remon tag & nail in East side of R.R. Tie fence post 2' West of tele cab box AZ. 195° 114.44'  
A.C. remon tag & nail in South side of Utility Pole AZ. 87° 71.10'  
"+" in North end of 12" C.M.P. on drive to West AZ. 272° 27.06'  
1/2" Rebar AZ. 270° 43.28'  
1/2" Rebar AZ. 270° 86.19'

Signed by *George J. Mitchell* Date 12-29-93  
Surveyor's Michigan License No. 19618