

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

MAR 16 1994

For corners in

County Allegan

Located in:

Corner Code #

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>1</u> N <u>R16</u> W | <u>K-4</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

1993 DEC 30 PM 2:45  
*James A. LeBette*  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICH.

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	10	9	8	7	6	5	4	3	2	1		
7												
8	19	18	17	16	15	14	13	12	11	10	9	8
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36						
13												

I, George J. Mitchell, in a field survey on December 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4

G.L.O. Notes	L.C.R.C. Recorded in Liber 2, Page 417	
Sugar 13" N70W 16lks	January 9, 1975	iron March 1987
Beech 12" S31E 3lks	Street Sign NW	37.3' Tele Pole SW 51.6'
	Power Pole NE	99.0' Tele Pole SE 53.2'
	26" Maple SE	101.7' Street Sign NW 40.7'
	Tele Cable Box NW	44.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4

Found 1-1/2" iron bar in monument box and accepted iron as a careful and faithful perpetuation of the position of original corner based on remaining witnesses and measurements north and east.

Power Pole	NE	99.0' (to face)
Tele Pole	SW	51.6'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4

Replaced 1-1/2" iron bar with A.C. remonumentation 3/4" iron & cap in mon. box

A.C. remon tag & nail in West side of Power Pole	AZ. 017°	99.26'
A.C. remon tag & nail in West side of 40" Maple	AZ. 171°	204.71'
A.C. remon tag & nail in East side of cut-off Pole with T.C. Box attached	AZ. 225°	51.10'
1/2" Rebar at edge of asphalt pavement	AZ. 317°	30.13'
CL of 109th Avenue	North	2.1'

Signed by *George J. Mitchell* Date 12-29-93  
 Surveyor's Michigan License No. 19618

LIBER 004 PAGE 337