

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Allegan (County) Located in: Casco Township Corner Code # K-13

1. Public Land Survey	T <u>1</u> N <u>pl 6</u> W	K-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1995 DEC 14 PM 2:32
FILED
Register of Deeds Stamp & File Number

SURVEY & REMONUMENTATION
APR 29 1996
COMMISSION

I, George J. Mitchell, in a field survey on November 11, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	10	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-13

SEP SHEET 2 OF 2



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13
FOUND PLOW POINT ON TOWNLINE FROM CORNER HISTORY AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

MEASURED 2632.80 FEET EAST TO L-13
MEASURED 2635.32 FEET WEST TO J-13

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON MAY 5, 1995

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 5-5-95
COUNTY REP. And L. Cambridge

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13
REPLACED PLOW POINT WITH 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.

A.C. remon tag & nail in SW side of Power Pole	AZ. 335°	82.12'
A.C. remon tag & nail in North side of 9" Ash	AZ. 75°	74.76'
A.C. remon tag & nail in East end of 14" CMP Pipe	AZ. 240°	85.22'
North face of Stopt Sign 12" above ground	AZ. 340°	52.25'
Geneva township Corner I-1	AZ. 270°	88.58'

SHEET 1 OF 2

Signed by George J. Mitchell Date November 11, 1995
Surveyor's Michigan License No. 19618

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JUL 28, 1971
REVISED MAY 14, 1975
REVISED JUL, 1983

CORNER HISTORY

K-13 TIN. R16W
 SW CORNER SECTION 36
 CASCO

1831 L. LYON - ORIGINAL CORNER SET @ 80 CH WEST OF SE CORNER
 HEMLOCK 12 N63E 12 LKS
 MAPLE 24 N72W 47 LKS

DATE UNKNWN - OLD SURVEY NOTES - SECTION 36 CASCO
 STAKE

NOTES SHOW 2627.8 FEET EAST TO STONE-STAKE & CROCKERY AT S1/4 POST
 MEASURES 2632.80' 1995

1966 RATEKIN CARD FILE
 PD. PLOW POINT
 TELE POLE SE 28.05'
 STREET SIGN NE 32.7'
 STOP SIGN NNW 47.85'

SHOWS STRAIGHT LINE FOR MILE TO THE EAST WITH DISTANCES OF 2634.29' TO
 S1/4 POST.

1987 RATEKIN SURVEY
 PD. PLOW POINT -MEASURED 2632.76' TO S1/4 POST AND 2632.46'
 (ON STRAIGHT LINE) FROM S1/4 POST TO SE CORNER SEC 36

2/1995 G. MITCHELL
 PD. PLOW POINT
 STOP SIGN NNW 52.20'
 POWER POLE NW 81.85'
 STOP SIGN SW 104.70'
 5/8" REBAR SOUTH 33.00'