

# REMONUMENTATION

APR 25 1995

## ALLEGAN COUNTY REMONUMENTATION

### COMMISSION

For corners in  
Allegan

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

(County)	Located In:	Corner Code #:
	Casco Township	
1. Public Land Survey	T <u>1</u> N R <u>16</u> W	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1994 DEC 16 AM 9:53  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY, MICHIGAN  
 [Signature]

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George J. Mitchell, in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-1 CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY  
 NO HISTORY AVAILABLE ON THIS CORNER

APPROVED REMONUMENTATION CORNER  
 P.A. 345 OF 1990  
 ALLEGAN COUNTY  
 DATE APPROVED 11-28-94  
 COUNTY REP. Mark L. Van Orden

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-1 NO CORNER FOUND. SET CORNER ON SPLIT DISTANCE BETWEEN K-1 AND M-1 ON AN EXISTING EAST-WEST FENCE AND OCCUPATION LINE AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL ESTABLISHMENT OF THE CORNERS LOCATION.

MEASURED 2615.91 FEET WEST TO K-1 & 2615.91 FEET EAST TO M-1



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-1 SET 3/4" X 36" IRON PIN WITH ALLEGAN CO. REMON CAP.  
 A.C. remon tag & nail in SW side of 18" Cherry AZ. 90° 1.97'  
 A.C. remon tag & nail in East side of 8" Cherry AZ. 347° 51.57'  
 A.C. remon tag & nail in South side of 20" Cherry AZ. 270° 99.22'  
 A.C. remon tag & nail in SW side of Power Pole AZ. 128° 120.43'  
 Ganges Township Corner L-13 AZ. 270° 21.88'

Signed by George J. Mitchell Date December 12, 1994  
 Surveyor's Michigan License No. 19618

LIBR 0005 PAGE 005