

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in  
Allegan

(County)

Located In: Corner Code ##

1. Public Land Survey

	T 2 N R 16 W	M-13 Ganges
	<u>T 1 N R 16 W</u>	<u>M-1 Casco</u> ✓
	T 2 N R 15 W	A-13 Clyde
	T 1 N R 15 W	A-1 Lee

2. Property Controlling in Section

S	T	R	
S	T	R	

3. Miscellaneous Property in Sec.

S	T	R	
S	T	R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1994 DEC 16 AM 9:53

FILED

Register of Deeds Stamp & File Number

I, George J. Mitchell in a field survey on December 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

T 1 N R 16 W

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1, M-13, A-1, A13

L. LYON 1831 SET POST 36.18 CHAINS WEST OF QUARTER POST. RANGE LINE 2 LKS NORTH OF TEMP POST. HEMLOCK 6 S39W 11 LKS BEECH 6 N49-1/2E 23 LKS	G. MITCHELL 1980 FD 5/8" IRON BAR ON EAST EDGE OF ROAD. 18" POPLAR NNW 115.2' POWER POLE SW 72.45' POWER POLE SOUTH 56.5'
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1, M-13, A-1, A-13  
FOUND 5/8 IRON BAR 12" DEEP ON EAST EDGE OF ROAD AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-29-94  
COUNTY REP. Rich A. Van Dine



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1, M-13, A-1, A-13  
REPLACED 5/8" IRON WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.

A.C. remon tag & nail in East side of Power Pole	AZ. 217°	72.66'
A.C. remon tag & nail in SW side of TCB Post	AZ. 340°	99.80'
A.C. remon tag & nail in East side of 40" Ash	AZ. 348°	115.21'
Center of a 4" White Pine	AZ. 56°	73.12'
Center of a 4" White Pine	AZ. 114°	46.47'
Center of north-south gravel road	AZ. 270°	10.0'

Signed by George J. Mitchell Date December 12, 1994  
Surveyor's Michigan License No. 19618