

RECEIVED
MAR 07 2000

FILED

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

FEB -1 AM 8:38

INDEXED 007 PART 164

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

ALLEGAN COUNTY..... Located in: ..CASCO..... Township
Corner Code #
1. Public Land Survey T.1 N.. R.16 W.M-12.....
T..... R..... E1/4 POST, SECTION 36
2. Property Controlling S..... T..... R.....
in Section S..... T..... R.....
3. Miscellaneous S..... T..... R.....
Property in Sec. S..... T..... R.....
4. Lot No., Recorded Plat
5. Private Claims.....

Jayne A. [Signature]
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

I, **George J. Mitchell, P.S.**, in a filed survey on **December 28, 1999** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town & range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12

SEE SHEET 2 OF 2 FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 5/8" REBAR FROM ACCESSORIES AS LISTED IN NO. 4 BY WIGHTMAN-MOORED. I DO NOT AGREE WITH THE 1987 SET POSITION OF THIS CORNER. 1928 HISTORY ON THIS CORNER CALLED FOR STONE ON STRAIGHT LINE SPLIT BETWEEN SECTION CORNERS (2641.98' FOR EACH HALF MILE). COULD NOT FIND STONE. I REESTABLISHED POSITION OF CORNER BY SETTING A STANDARD ALLEGAN CO. REMON. AT MIDPOINT AND ON LINE BETWEEN SECTION CORNERS (2642.10' FOR EACH HALF MILE), AND IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

THIS CORNER WAS APPROVED BY THE ALLEGAN COUNTY SURVEYORS PEER GROUP ON DECEMBER 28, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

EAST QUARTER POST, SECTION 36, TOWN 1 NORTH, RANGE 16 WEST.

STANDARD ALLEGAN CO. REMON. MONUMENT (3/4" X 24" STEEL ROD WITH RED CAP)

- A.C. REMON TAG & NAIL IN SOUTH SIDE OF POWER POLE
- A.C. REMON TAG & NAIL IN NORTH SIDE OF 10" TWIN MAPLE
- A.C. REMON TAG & NAIL IN EAST SIDE OF 40" MAPLE
- A.C. REMON TAG & NAIL IN SOUTHWEST SIDE OF 24" MAPLE
- 5/8" REBAR
- CENTERLINE OF 60TH STREET
- W1/4 POST, SECTION 31, TOWN 1 NORTH, RANGE 15 WEST

- AZ. 080° 65.35 FEET
- AZ. 270° 58.35 FEET
- AZ. 335° 94.00 FEET
- AZ. 145° 41.38 FEET
- AZ. 270° 5.90 FEET
- AZ. 090° 2.5 FEET
- AZ. 180° 31.40 FEET

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED DEC. 28 1999
COUNTY REP. *[Signature]*

Signed by *George J. Mitchell* Date 12/30/99

Surveyor's Michigan License No.19618.....



MAR 07 2000

SECTION

GOVERNMENT CORNER HISTORY

EAST QUARTER POST OF SECTION 36
TOWN 1 NORTH, RANGE 16 WEST

M-12

1. C. BRITAIN D.S. 1831 SET POST AT 40 CHAINS
BEECH 7 S27W 27 LKS
BEECH 4 N41W 32 LKS
2. OLD NOTES (NO DATE) HUGH MCDOUGHAL NOTES SHOW STONE WITH DISTANCE OF 40.10 CH. (2646.6') SOUTH TO SE CORNER AND 39.76 CH. (2624.16') NORTH TO NE CORNER.
3. M. PECK 1928 FROM COUNTY ROAD COMMISSION RECORDS
STONE
24" MAPLE N22W 86.4'
15" MAPLE N84W 31.8'
10" MAPLE S27E 43.7'
RECORDS SHOW 1/4 POST ON STRAIGHT LINE SPLIT BETWEEN SECTION CORNERS. 2641.98' FOR EACH HALF MILE.
4. WIGHTMAN-MOORED MAY 1987 SET 1/2" IRON BY DOUBLE DISTANCE FROM E1/8 POST IN THE SE1/4 AND THE SE CORNER OF THE SECTION ON EXTENDED LINE.
CL 60TH STREET EAST 11'
19" MAPLE SE 44.15'
POWER POLE ENE 70.90'
IN LINE WITH DRIVE TO EAST
SW COR T.C.B. SE 60.15'
SURVEY SHOWS DISTANCE OF 2642.04' N00° 25' 38"W TO NE CORNER & 2641.68' S00° 40' 59"E TO SE CORNER.
5. G. MITCHELL P.S. 1991 & 1995 & 1998 FD 5/8" REBAR
CL 60TH STREET EAST 10.5'
IRON WEST 33'
18" MAPLE SE 44.0'
W1/4 POST, SEC 31, LEE TWP. S20E 31.95'
6. G. MITCHELL P.S. 1999 FOUND 5/8" REBAR FROM ACCESSORIES AS LISTED IN NO. 4 BY WIGHTMAN-MOORED. COULD NOT FIND STONE AS CALLED FOR IN NO. 3 ON STRAIGHT LINE SPLIT BETWEEN SECTION ORNERS. REESTABLISHED CORNER ON STRAIGHT LINE SPLIT BETWEEN SECTION CORNERS.