

ALLEGAN COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan

(County)

Located in:

Corner Code #

Lee Township

1. Public Land Survey

T 1 N R 15 W

A-13

T R

T 1 N R 16 W

M-13

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

1994 DEC 16 AM 9:54
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN

1994 DEC 16 AM 9:54

FILED

Register of Deeds Stamp & File Number

T1N, R15W

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, George J. Mitchell, in a field survey on December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners; all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 1837 W. BROOKFIELD SET @ 80 CHAINS RATEKIN WITNESS CARD 1966 & 1987
SUGAR MAPLE 24 N70-1/2E 18 LKS POUND IRON & WOOD STAKE
CHERRY 24 N75-2/3W 99 LKS POWER POLE ESE 57.63' CK 1994
POWER POLE WNW 97.4' CK 1994
1890 - SURVEY BOOK - FD STONE STREET SIGN POST SSE 17.5 CK 1994
TELE CABLE BOX WSW 28.1' GONE 1994
MITCHELL 1989 - FOUND 5/8" IRON BAR
POWER POLE NE 57.8' CK 1994
POWER POLE WNW 97.4' CK 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 FOUND 5/8" IRON FROM ABOVE WITNESSES AND ACCEPTED ITS LOCATION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

REMON
NOV 1994
COM

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-29-94
COUNTY REP. *George J. Mitchell*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 REPLACED IRON WITH 3/4" X 36" PIN WITH ALLEGAN CO. REMON CAP.
A.C. remon tag & nail in South side of Power Pole AZ. 75° 57.78'
A.C. remon tag & nail in West side of Anchor Post AZ. 105° 60.28'
A.C. remon tag & nail in South side of Power Pole AZ. 275° 97.23'
A.C. remon tag & nail in SE side of 40" Willow AZ. 25° 90.34'
Van Buren County Corner AZ. 270° 120.79'

Signed by George J. Mitchell Date December 6, 1994
Surveyor's Michigan License No. 19618

LIFE 0005 PAGE 023